


3/16/10 9:30 AM

SOUTH FLORIDA WATER MANAGEMENT DISTRICT

North Palm Beach County – Part 1 CERP

Palm Beach County Board of County
Commissioners Workshop
March 16, 2010

*Kenneth G. Ammon, P.E.
Deputy Executive Director
Everglades Restoration and Capital Projects*



Project Planning Objectives

- Reduce or reverse saltwater intrusion and subsequent environmental impacts to NW Fork Loxahatchee River ecological communities
- Improve environmental and public water supply by utilizing freshwater sources currently lost to tide
- Restore wetland hydroperiods within watershed
- Restore hydrologic and spatial connectivity of natural areas
- Reduce adverse impacts of accumulated sediment and reduce sediment loading to Lake Worth Lagoon (LWL) from C-51
- Maintain or improve current level of flood protection in the L-8 basin

sfwmd.gov




Completed Project Activities

- Completed Watershed Assessment and Existing Conditions 2004
- Feasibility Scoping Meeting 2005
- Identified Future Conditions 2006
- Finalized Problems, Opportunities, Constraints, Performance Measures and Targets 2007
- Impact Evaluation for Grassy Waters Preserve 2007
- Identification and refinement of management measures and alternatives Ongoing
- LECsR Alternatives modeling completed 2009
- Flow-way 3 modeling completed 2010



Recent Project Activities

- Finalized Alternatives for Analysis
- Continued development of management measures associated with each alternative
- Conducted revised Flow-way 3 and Grassy Water Preserve model runs
- Completed Draft Habitat Unit (HU) Calculations
- Began evaluation of impacts (NEPA)
- Generated Planning Level Costs




Planning Flow Chart



Final Array of Alternatives and Key Components

- Eight alternatives under consideration
- Range of alternative components
 - Four alternatives which use 3 different flow-ways with storage reservoirs ranging from 2,800 to 90,000 acre foot storage
 - One alternative which uses natural flow connectivity (no reservoirs or STAs)
 - One alternative which uses tributary flow from C-44
 - Moss property restoration
 - Lake Worth Lagoon sediment reduction and management
 - Best alternatives will be combined to meet project objectives
- Draft planning level costs range from \$44M-\$851M



CERP Possible Storage and Flow-way Improvements

(4A) Flow-way 4 (use existing canals to convey water from C-44 to Cypress Creek) – STA required

(3B, 3D) Flow-way #3
(lands have been acquired)

(6A) Moss Property Improvements

(2B) Flow-way #2

(1B) L-8 Reservoir
(acquired - 46,000 acre feet capacity, additional infrastructure required)


(1D) Additional Reservoir Storage, 44,000 acre feet capacity (not acquired)

(5B) Flow-way #1 and 2 combined

(1B, 1D) Flow-way #1
(flow path existing)

G-160 (constructed)

G-161 (constructed)



Flow-way #1




L-8 Reservoir

- Land acquired
- Additional infrastructure needed to realize project benefits
 - High head pump station (outflow)
 - Inflow structure
 - Embankment modifications for erosion and wave run-up



Control #2 Pump Station (will require modification)



SOUTH FLORIDA WATER MANAGEMENT DISTRICT

G-161 Northlake Boulevard Structure (constructed)




SOUTH FLORIDA WATER MANAGEMENT DISTRICT

G-160 Loxahatchee Slough Structure (constructed)




Flow-way #2



SOUTH FLORIDA WATER MANAGEMENT DISTRICT

Flow-way 3 Acquired Properties




Flow-way 4: Initial Alt 4A



sfwmd.gov

Lake Worth Lagoon Alternative



Measure	Description
LWLA.1	Dredge C-51 Canal Upstream of S-155 and Incorporate Sediment Trap
LWLA.3.a	Cap Sediment and Restore Habitat at Bingham Island Location
LWLA.3.b	Cap Sediment and Restore Habitat at Town of Palm Beach Location
LWLA.3.c	Cap Sediment and Restore Habitat at Shallow Island Location
LWLA.3.d	Cap Sediment and Restore Habitat at New Snook Island Location
LWLA.3.e	Cap Sediment and Restore Habitat at Ibis Isle Location
LWL B.1	Provide Sediment Trap Upstream of S-155 Structure
LWL F.3	Restore Oyster Habitat at Johns Island Site
LWL F.4	Provide Educational / Recreational Measures at Bryant Park/Snook Island

Constructed Project Facilities, Land Acquired and Costs

■ L-8 Reservoir*	\$220,279,535
■ G-160 Water Control Structure	\$2,123,615
■ G-161 Water Control Structure	\$2,085,084
■ Flow-way 3 Lands (Nine-Gems, Cypress Creek, Gulfstream and Shiloh Farms, Culpepper Ranch)	\$113,578,235
■ Flow-way 1 Lands (Loxahatchee Slough properties) *	\$38,540,000
■ Lake Worth Lagoon	\$4,100,000
■ Total	\$380,706,469

*additional infrastructure required



Benefit Analyses



Wetland / Upland Benefits

- WRAP / Hydrology Analysis
- Loxahatchee River Floodplain
- Hydrologic and Spatial Connectivity

Estuarine Benefits

- Substrate Improvement
- Suspended Sediment Removal



Draft Habitat Units/Ecological Lift Acres and Preliminary Cost by Alternative

	Acres	Cost/H.U.	Acres	Cost/H.U.
■ FWO*	-	-	■ 3B - 8,751	(\$ 30,000)
■ 1B - 11,136		(\$41,000)	■ 3D - 9,687	(\$ 25,000)
■ 1D - 11,367		(\$75,000)	■ 4A - 174	(\$695,000)
■ 2B - 5,975		(\$75,000)	■ 6A - 2,549	(\$ 18,000)
			■ LWL** - 641	(\$ 69,000)

*Future Without Project Condition

**Lake Worth Lagoon



sfwmd.gov

Benefit Analysis and Performance Measures

NW Fork Loxahatchee River Goals

Alternative	Percentage of Time Wet Season Target Met	Percentage of Time Dry Season Target Met	Percentage of Time Transition Month (June & November) Target Met	Number of Times MFL Exceeded
2050B (FWO)	67%	49%	72%	34
1B	83%	89%	86%	2
1D	83%	92%	88%	0
2B	92%	94%	100%	1
5B	97%	95%	95%	2


Pending Unresolved Issues

- Pump Sizing Contingent upon selected alternative and associated flow regimes
- Risk and uncertainty regarding water quality limitations to Grassy Waters Preserve and Loxahatchee Slough
- Water Resource Development Act as it affects cost share credit for previous and future construction



Next Steps

- Finalize
 - Gross (order of magnitude) land costs
 - Alternative costs and benefits
 - Evaluation of alternatives against performance measures and targets
 - Evaluation of impacts
- Select Tentatively Selected Plan with PDT
- Finalize Alternative Formulation Briefing Document
- Package modeling products for Independent Technical Review
- Conduct Technical Review Briefing of AFB Document



Schedule

- Select Tentatively Selected Plan with PDT 30-Mar-2010
- Alternative Analysis and Draft AFB Document 1-May-2010
- Submit Final AFB Document to COE for Review
(incorporate PDT, RECOVER, SAJ Comments) 20-May-2010
- Technical Review Briefing (TRB) and Agency
Technical Review (ATR) - 17-Jun- 2010
- Receive ATR Certification – 23- Sep-2010
- Submit AFB Package to SAD – 10-Dec-2010
- AFB Meeting – 25-Jan-2011
- Receive Final AFB Guidance Memorandum – 28-Jan 2011
- Draft PIR* – 20-Oct-2011
- Final PIR* - 11-Apr-2012

*standard COE time frame post AFB

sfwmd.gov



QUESTIONS?

