

Agenda Item is over 50 pages; may be viewed in the Minutes Department

Agenda Item #: 3-C-2

**PALM BEACH COUNTY
BOARD OF COUNTY COMMISSIONERS
AGENDA ITEM SUMMARY**

Meeting Date: April 19, 2016

Consent

Regular

Workshop

Public Hearing

Department:

Submitted By: Engineering & Public Works

Submitted For: Roadway Production Division

EXECUTIVE BRIEF

Motion and Title: Staff recommends motion to approve: a contract with Dickerson Florida, Inc. (Dickerson) in the amount of \$883,590 for the construction of County Road 880 Twenty Mile Bend Slope Protection (Project).

SUMMARY: Approval of this contract will allow Palm Beach County to issue a notice to proceed to Dickerson, a St. Lucie County company, to begin construction of the Project. The Palm Beach County Small Business Enterprise (SBE) goal for all projects is 15% overall. The SBE participation proposed for the Project by Dickerson is 15.49%.

District 6 (MRE)

Background and Justification: Bids for the Project were received by the Engineering Department on February 9, 2016. Dickerson was the lowest responsive, responsible bidder. The Office of Small Business Assistance issued its evaluation on February 26, 2016. Time to complete all work under this contract shall be no more than 120 calendar days. Approximately 1000' of slope protection will be installed under this contract.

Attachments:

1. Location Sketch
2. Contracts
3. Contract Pages C-1 and C-2
4. SBE Evaluation Letter
5. Bid Tabulation

Recommended by:

Ornelis A Fernandez
Division Director

Date

3/18/16

Approved By:

A. T. Webb
County Engineer

Date

3/22/16

II. FISCAL IMPACT ANALYSIS

A. Five Year Summary of Fiscal Impact:

Fiscal Years	2016	2017	2018	2019	2020
Capital Expenditures	\$972,798	-0-	-0-	-0-	-0-
Operating Costs	-0-	-0-	-0-	-0-	-0-
External Revenues	-0-	-0-	-0-	-0-	-0-
Program Income (County)	-0-	-0-	-0-	-0-	-0-
In-Kind Match (County)	-0-	-0-	-0-	-0-	-0-
NET FISCAL IMPACT	\$972,798	-0-	-0-	-0-	-0-
# ADDITIONAL FTE POSITIONS (Cumulative)	_____	_____	_____	_____	_____

Is Item Included in Current Budget? Yes X No

Budget Account No:
 Fund 3500 Dept 361 Unit 1490 Object 6551



Recommended Sources of Funds/Summary of Fiscal Impact:
 Transportation Improvement Fund
 CR880 Canal Bank Stabilization Phase II

Construction Contract	\$883,590.00
Contingency	\$ 26,508.00
Testing Lab	\$ 1,000.00
Staff Costs	
-Roadway Production	\$ 17,600.00
-Survey Section	\$ 8,800.00
-Construction Coordination	\$ 35,300.00
FISCAL IMPACT	\$972,798.00

C. Departmental Fiscal Review: *Alicia Kovalainen*

III. REVIEW COMMENTS

A. OFMB Fiscal and/or Contract Dev. and Control Comments:

 Steven B. Mum 3/22 P60 OFMB 3/23	 Dr. J. J. Furubault Contract Dev. and Control 3/28/14
--	---

B. Approved as to Form and Legal Sufficiency:


Markus R. Gustafson 3/29/14
 Assistant County Attorney

C. Other Department Review:

 Department Director

This summary is not to be used as a basis for payment.

**PROJECT LOCATION
COUNTY ROAD 880 TWENTY MILE BEND
SLOPE PROTECTION - PHASE II
PALM BEACH COUNTY PROJECT NO. 2015525**



LOCATION MAP

CONTRACT

STATE OF FLORIDA)

) SS

COUNTY OF PALM BEACH)

This Contract, made this ____ day of _____, A.D. 2016, by and between PALM BEACH COUNTY, a Political Subdivision of the State of Florida, (hereinafter "County"), and Dickerson Florida, Inc. of Ft. Pierce, Florida, and their heirs, executors, administrators and assigns, (hereinafter "Contractor"):

WITNESSETH: The Contractor agrees with the County, for the consideration herein mentioned at their own proper cost and expense to do all the work and furnish all necessary labor, materials, equipment, machinery, tools, apparatus, services, state workmen’s compensation and unemployment compensation taxes incurred in the performance of the contract, and means of transportation for the complete construction of:

PROJECT NAME: COUNTY ROAD 880 TWENTY MILE BEND SLOPE PROTECTION

PROJECT NO.: 2015525

IN THE AMOUNT OF:
EIGHT HUNDRED EIGHTY THREE THOUSAND FIVE HUNDRED NINETY DOLLARS 00/1000

(IN WORDS)

\$883,590.00
(IN FIGURES)

in Palm Beach County, Florida, in the manner and to the full extent as set forth in the Contract Documents therefore and the Contract Documents relative thereto, are made a part of this Agreement as completely as if set forth herein, to the satisfaction of the County, or its duly authorized representative.

The Contractor further agrees for the consideration herein mentioned to commence the work with adequate forces and equipment within fourteen (14) calendar days of the date set forth in the "Notice to Proceed". The time limit for the completion of all work under this contract shall be one hundred twenty (120) calendar days, (see Special Provisions). The date fixing this period upon the calendar shall be established and stated in the "Notice to Proceed". After commencement of the work, it shall be properly dispatched toward completion, to the satisfaction of the Engineer, and shall be fully completed within the time limit. It is understood and agreed that the time limit for completion of said work is the essence of the contract and should the Contractor fail to complete the work within the time limit, it is agreed that for such calendar day that any work provided for in these Contract Documents shall remain incomplete after the time limit has expired, including any official extension of the time limit; the sum per day given in the contained schedules shall be deducted from monies due the Contractor, not as a penalty, but as liquidated damages (in accordance with Section 8-10.2 of the Standard Specifications) and added expense for supervision.

The Contractor shall take into account all contingent work which has to be done by other parties arising from any cause whatsoever, and shall not plead his want of knowledge of such contingent work as an excuse for delay in his work, or for its non-performance.

IN WITNESS WHEREOF, the parties have caused this Contract to be executed and sealed the day and year first written above.

ATTEST:

SHARON R. BOCK,
Clerk & Comptroller

PALM BEACH COUNTY, FLORIDA, a
Political Subdivision of the
State of Florida

BOARD OF COUNTY COMMISSIONERS

By: _____
Deputy Clerk

By: _____
Mary Lou Berger, Mayor

APPROVED AS TO FORM
AND LEGAL SUFFICIENCY

[Signature]
APPROVED AS TO TERMS
AND CONDITIONS

[Signature]
(witness signature)

Dickerson Florida, Inc.
(Corporate Name)

ANTOINETTE PETERSON
(witness name printed)

a Florida corporation
(insert state of incorporation)

[Signature]
(witness signature)

By *[Signature]*
(signature)


RICHARD J. FORLIFER
(witness name printed)

Larry T. Dale
(print signatory's name)

Its President
(print title)

MARCH 7, 2010
(date)

(Corporate Seal)



Office of
Small Business Assistance
50 South Military Trail, Suite 202
West Palm Beach, FL 33415
(561) 616-6840
Fax: (561) 616-6850
www.pbcgov.com/osba



**Palm Beach County
Board of County
Commissioners**

- Mary Lou Berger, Mayor
- Hal R. Valeche, Vice Mayor
- Paulette Burdick
- Shelley Vana
- Steven L. Abrams
- Melissa McKinlay
- Priscilla A. Taylor

County Administrator

Verdenia C. Baker

"An Equal Opportunity
Affirmative Action Employer"

DATE: February 26, 2016
TO: Holly B. Knight, P.E., Contracts Section
Manager - Roadway Production Division
Through: Tonya Davis Johnson, Director of Office of
Small Business Assistance
FROM: Tanoy Williams, Small Business Development
Specialist II
SUBJECT: Compliance Review on Project No. 2015525
County Road 880 Twenty Mile Bend Slope
Protection

The following is Compliance Review of SBE participation on the above-mentioned project. (Base Bid + Alternate 1)

LOW BIDDER: DICKERSON FLORIDA, INC.
3122 N. 25th Street
Fort Pierce, FL 34946
Phone: 772-429-4444
Bid Opening: 02-09-2016
Bid Amount: \$883,590.00
Goal: 15% Overall
Goal Achieved: 15.49%

SBE Participation:
(BL) OC UNLIMITED \$136,956.05 15.49%



2ND LOW BIDDER: **ARBOR TREE & LAND, INC.**
5796 WESTERN WAY
LAKE WORTH, FL 33463
Phone: 561-722-5626
Bid Amount: \$1,152,137.82
Goal: **15% Overall**
Goal Achieved: **16.09%**

SBE Participation:
(SB) Habana Excavating **\$185,400.00** **16.09%**

THIRD LOW BIDDER: **H & R OF BELLE GLADE, INC**
40200 Hatcher Road
Belle Glade, FL 33430
Phone: 561-723-5735
Bid Amount: \$1,187,975.00
Goal: **15% Overall**
Goal Achieved: **2.40%**

SBE Participation:
(SB) DENNIS J. LEAVY **\$28,600.00** **2.40%**

EVALUATION

The low bidder **DICKERSON FLORIDA, INC.**
has met the SBE goal for this project.

cc: Helene Hvizd, Assistant County Attorney
File

COUNTY ROAD 880
 TWENTY MILE BEND SLOPE PROTECTION
 PBC PROJECT #2015525

ATTACHMENT 5
PAGE 1 OF 3

				ENGINEERS ESTIMATE	BID AVERAGE	Dickerson Florida, Inc.		Arbor Tree & Land, Inc.		H&R of Belle Glade, Inc.	
ITEM #	DESCRIPTION	QTY	UNIT	UNIT PRICE	UNIT PRICE	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	UNIT PRICE	TOTAL
BASE BID ITEMS											
101-1	Mobilization	1	LS	\$265,000.00	\$ 116,888.20	\$100,000.00	\$ 100,000.00	\$ 165,192.00	\$ 165,192.00	\$ 25,100.00	\$ 25,100.00
102-1	Maintenance of Traffic	1	LS	\$40,000.00	\$ 16,808.80	\$ 10,000.00	\$ 10,000.00	\$ 3,000.00	\$ 3,000.00	\$ 8,700.00	\$ 8,700.00
102-99	Variable Message Board	28	DAY	\$35.00	\$ 95.90	\$ 25.00	\$ 700.00	\$ 197.00	\$ 5,516.00	\$ 175.00	\$ 4,900.00
102-11	Off Duty Police Officer	24	HR	\$79.00	\$ 64.30	\$ 60.00	\$ 1,440.00	\$ 45.00	\$ 1,080.00	\$ 75.00	\$ 1,800.00
110-11	Clearing and Grubbing	1	LS	\$22,709.74	\$ 37,721.80	\$ 50,000.00	\$ 50,000.00	\$ 9,000.00	\$ 9,000.00	\$ 62,100.00	\$ 62,100.00
120-5	Channel Excavation	5,360	CY	\$33.25	\$ 29.20	\$ 11.00	\$ 58,960.00	\$ 3.00	\$ 16,080.00	\$ 47.00	\$ 251,920.00
0339-1	Miscellaneous Asphalt Pavement	47	TN	\$388.00	\$ 339.80	\$ 300.00	\$ 14,100.00	\$ 344.00	\$ 16,168.00	\$ 265.00	\$ 12,455.00
514-71-2	Filter Fabric, Plastic, Stabilization	3,663	SY	\$14.00	\$ 12.84	\$ 5.00	\$ 18,315.00	\$ 3.20	\$ 11,721.60	\$ 20.00	\$ 73,260.00
530-3-3	Rip-Rap Rubble, Bank & Shore	3,663	SY	\$95.00	\$ 115.99	\$ 100.00	\$ 366,300.00	\$ 165.44	\$ 606,006.72	\$ 103.00	\$ 377,289.00
530-74	Bedding Stone	1,544	TN	\$69.00	\$ 50.90	\$ 40.00	\$ 61,760.00	\$ 35.00	\$ 54,040.00	\$ 54.00	\$ 83,376.00
530-74	Fill Sand-57 Stone or Larger (50:50 Mix)	1,775	TN	\$34.50	\$ 63.42	\$ 30.00	\$ 53,250.00	\$ 38.10	\$ 67,627.50	\$ 42.00	\$ 74,550.00
536-1-1	Guardrail, Roadway,W-Beam	94	LF	\$20.25	\$ 28.80	\$ 25.00	\$ 2,350.00	\$ 26.00	\$ 2,444.00	\$ 40.00	\$ 3,760.00
538-1	Guardrail - Reset	942	LF	\$10.00	\$ 18.20	\$ 20.00	\$ 18,840.00	\$ 21.00	\$ 19,782.00	\$ 20.00	\$ 18,840.00
10-1	Pipe Abandonment Flowable Fill	70	CY	\$750.00	\$ 368.00	\$ 230.00	\$ 16,100.00	\$ 200.00	\$ 14,000.00	\$ 760.00	\$ 53,200.00
10-2	Pipe Extension & Collar	2	EA	\$10,000.00	\$ 11,119.40	\$ 5,000.00	\$ 10,000.00	\$ 5,000.00	\$ 10,000.00	\$ 30,000.00	\$ 60,000.00
SUBTOTAL BASE BID							\$ 782,115.00		\$ 1,001,657.82		\$ 1,111,250.00
ALTERNATE 1											
120-1	Regular Excavation	9,900	CY	\$31.50	\$ 19.44	\$ 10.25	\$ 101,475.00	\$ 15.20	\$ 150,480.00	\$ 7.75	\$ 76,725.00
SUBTOTAL ALTERNATE 1							\$ 101,475.00		\$ 150,480.00		\$ 76,725.00

TOTAL BID AMOUNT (WITHOUT ALTERNATE 1)	\$ 782,115.00	\$ 1,001,657.82	\$ 1,111,250.00
TOTAL BID AMOUNT (BASE BID + ALTERNATE 1)	\$ 883,590.00	\$ 1,152,137.82	\$ 1,187,975.00

COUNTY ROAD 880
 TWENTY MILE BEND SLOPE PROTECTION
 PBC PROJECT #2015525

Engecon Construction, Inc.	Shoreline Foundation, Inc.
----------------------------	----------------------------

ITEM #	DESCRIPTION	QTY	UNIT	Engecon Construction, Inc.		Shoreline Foundation, Inc.		
				UNIT PRICE	TOTAL	UNIT PRICE	TOTAL	
BASE BID ITEMS								
101-1	Mobilization	1	LS	\$ 195,500.00	\$ 195,500.00	\$ 98,649.00	\$ 98,649.00	
102-1	Maintenance of Traffic	1	LS	\$ 36,000.00	\$ 36,000.00	\$ 26,344.00	\$ 26,344.00	
102-99	Variable Message Board	28	DAY	\$ 22.00	\$ 616.00	\$ 60.50	\$ 1,694.00	
102-11	Off Duty Police Officer	24	HR	\$ 50.00	\$ 1,200.00	\$ 91.50	\$ 2,196.00	
110-11	Clearing and Grubbing	1	LS	\$ 34,000.00	\$ 34,000.00	\$ 33,509.00	\$ 33,509.00	
120-5	Channel Excavation	5,360	CY	\$ 27.00	\$ 144,720.00	\$ 58.00	\$ 310,880.00	
0339-1	Miscellaneous Asphalt Pavement	47	TN	\$ 300.00	\$ 14,100.00	\$ 490.00	\$ 23,030.00	
514-71-2	Filter Fabric, Plastic, Stabilization	3,663	SY	\$ 15.00	\$ 54,945.00	\$ 21.00	\$ 76,923.00	
530-3-3	Rip-Rap Rubble, Bank & Shore	3,663	SY	\$ 130.00	\$ 476,190.00	\$ 81.50	\$ 298,534.50	
530-74	Bedding Stone	1,544	TN	\$ 70.00	\$ 108,080.00	\$ 55.50	\$ 85,692.00	
530-74	Fill Sand-57 Stone or Larger (50:50 Mix)	1,775	TN	\$ 70.00	\$ 124,250.00	\$ 137.00	\$ 243,175.00	
536-1-1	Guardrail, Roadway,W-Beam	94	LF	\$ 23.50	\$ 2,209.00	\$ 29.50	\$ 2,773.00	
538-1	Guardrail - Reset	942	LF	\$ 13.00	\$ 12,246.00	\$ 17.00	\$ 16,014.00	
10-1	Pipe Abandonment Flowable Fill	70	CY	\$ 325.00	\$ 22,750.00	\$ 325.00	\$ 22,750.00	
10-2	Pipe Extension & Collar	2	EA	\$ 12,150.00	\$ 24,300.00	\$ 3,447.00	\$ 6,894.00	
SUBTOTAL BASE BID						\$ 1,251,106.00		\$ 1,249,057.50
ALTERNATE 1								
120-1	Regular Excavation	9,900	CY	\$ 24.00	\$ 237,600.00	\$ 40.00	\$ 396,000.00	
SUBTOTAL ALTERNATE 1						\$ 237,600.00		\$ 396,000.00

TOTAL BID **\$ 1,251,106.00** **\$ 1,249,057.50**

TOTAL BID / **\$ 1,488,706.00** **\$ 1,645,057.50**

ATTACHMENT 5
 PAGE 2 OF 3

**COUNTY ROAD 880
 TWENTY MILE BEND SLOPE PROTECTION
 PBC PROJECT #2015525**

*THE ITEMS AND QUANTITIES SHOWN, SHALL GOVERN OVER THE PLANS.
 PAY ITEM FOOTNOTES IN CONSTRUCTION PLANS SHALL ALSO BE INCLUDED IN ITEM UNIT PRICE.*

ATTACHMENT 5
 PAGE 3 OF 3

PAY ITEM FOOTNOTES:		
All items shall include cost to furnish and install.		
101-1	Mobilization	Includes NPDES Erosion Control Measures
102-1	Maintenance of Traffic	Includes all provision and maintenance of necessary signs, advanced warning, variable message boards, all detour signs and barricades at each end of CR880 for the duration of the project.
120-1	Regular Excavation	Includes removal and disposal
120-5	Channel Excavation	Includes removal and disposal
514-71-2	Filter Fabric, Plastic, Stabilization	Includes 4 foot minimum overlap, end burial, staking and wrapping at termination locations
530-3-3	Riprap - Rubble, Bank & Shore	Includes Keystone excavation wrapping and placement at the toe of slope
530-74	Bedding Stone	Includes Bedding Stone under Rip Rap
530-74	Fill Sand-57 Stone or Larger (50:50 Mixture)	Fill Sections
536-1	New Guardrail	Includes removal of the existing guardrail
538-1	Guardrail - Reset	Includes replacement of damaged posts, offset blocks, guardrail panel, hardware and reflectors
10-1	Pipe Abandonment Flowable Fill	Includes cleaning pipe, grouting with flowable fill and bricking ends
10-2	Pipe Extension & Collar	Includes upto 20'-0" of pipe extension, survey and labor to locate pipes, cleaning pipes, construction of concrete pipe collar and any dewatering

*Working days to complete project: 120 calendar days, (See Special Provisions).
 Bids as read at opening on Tuesday, February 9, 2016; 2:00 PM
 All bids subject to OSBA SBE compliance and Board Approval.
 Prepared by: Donna Lewis, Technical Assistant III
 Checked by: Holly B. Knight, P.E., Contracts Section Manager*