

**PALM BEACH COUNTY  
BOARD OF COUNTY COMMISSIONERS  
AGENDA ITEM SUMMARY**

REVISED

---

<b>Meeting Date:</b>	July 12, 2016	<b>Consent [X] Public Hearing [ ]</b>	<b>Regular [ ]</b>
----------------------	---------------	---	--------------------

**Department:** Water Utilities Department

---

**I. EXECUTIVE BRIEF**

**Motion and Title:** **Staff recommends motion to approve:** Change Order No. 1 to the Contract with AKA Services, Inc. (R2015-1033) for a revised scope of work, decreasing the contract price by \$135,113.72.



**Summary:** On August 18, 2015, the Board of County Commissioners approved a Contract with AKA Services, Inc. (R2015-1033) for the construction of 16" and 12" PVC water mains along SR 15 and Gator Blvd. in Belle Glade (Project). The Project is part of improvements to the water distribution system in the Glades Region that are being undertaken to improve service levels and system reliability through the replacement of aging infrastructure. The Project will provide for the construction of a new 16-inch water main to replace an existing water main along State Road 80 (Hooker Highway). Change Order No. 1 is necessary to address a revision in the scope of work due to changed conditions and will result in a decrease in the contract price. The Small Business Enterprise (SBE) participation goal established by SBE ordinance (R2002-0064) is 15% overall. This Contract provides for 15% SBE participation. AKA Services, Inc. is a local company. (WUD Project No. 13-052) District 6 (MJ)

**Background and Justification:** Change Order No. 1 authorizes the Contractor to perform the revised scope of work, contract overrun/underruns, directional drilling, removal and installation of the existing bike path, maintenance of traffic along Gator Blvd., additional soil testing along the redesign route, water services, additional utility exploration, furnishing and installation of tapping valves, furnishing and installation of handicap ramps along Gator Blvd. and additional striping along Gator Blvd. This work is necessary due to a change in conditions discovered on the work site.

**Attachments:**

1. Location Map
2. Two (2) Original Change Order No. 1

---

<b>Recommended By:</b>	 <b>Department Director</b>	<b>7-8-16</b> <b>Date</b>	
<b>Approved By:</b>	 <b>Assistant County Administrator</b>	<b>7-11-16</b> <b>Date</b>	

## II. FISCAL IMPACT ANALYSIS

### A. Five Year Summary of Fiscal Impact:


Fiscal Years	2016	2017	2018	2019	2020
Capital Expenditures	<u>(\$135,114)</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>
External Revenues	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>
Program Income (County)	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>
In-Kind Match County	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>
NET FISCAL IMPACT	<u>(\$135,114)</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>
# ADDITIONAL FTE POSITIONS (Cumulative)	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>

Budget Account No.: Fund 4011 Agency 721 Org. W038 Object 6543

Is Item Included in Current Budget? Yes No


Reporting Category N/A

### B. Recommended Sources of Funds/Summary of Fiscal Impact:

C. Department Fiscal Review: 

## III. REVIEW COMMENTS

### A. OFMB Fiscal and/or Contract Development and Control Comments:

 7/8/16  
Er 6/2 OFMB 7/8/2016

 7/8/16  
Contract Development and Control

### B. Legal Sufficiency:

 7/8/16  
Assistant County Attorney

### C. Other Department Review:

\_\_\_\_\_  
Department Director

This summary is not to be used as a basis for payment.






Palm Beach County  
Water Utilities  
Department  
Service Area (SA) and  
Major Facilities

WUD 13-052

Legend

- ★ Administration
- WTP Water Treatment Plant
- RAV Reclamation Facility
- WRWF Wastewater Reclamation Facility
- WWTP Wastewater Treatment Plant
- Mandatory Reclaimed SA
- - - - - Palm Beach County Limits
- Yellow P.B.C.W.U.D. Service Area



CHANGE ORDER

PROJECT: SR 15 and Gator Blvd water main Extension  
WATER UTIL. DEPT. PROJECT NO. WUD 13-052  
DISTRICT NUMBER: 6  
CHANGE ORDER NO.: One (1)

TO:	DOCUMENT NO.	R2015-1033
AKA Services, Inc	CONTRACT DATE:	August 18, 2015
15551 Okeechobee Blvd	NOTICE TO PROCEED:	Nov 30, 2015
Loxahatchee, Florida 33470	BUDGET LINE ITEM:	4011-721-W038-6543

You are directed to make the following changes in this contract:

1.1 Delete Line Item No 7	(\$176,400.00)
1.2 Delete Line Item No 9	(\$195,000.00)
1.3 Delete Line Item No 11	(\$40,000.00)
1.4 Delete Line Item No 15	(\$252,000.00)
1.5 Delete Line Item No 55	(\$13,500.00)
1.6 Add to Line Item No 6	\$126,000.00
1.7 Add to Line Item No 8	\$136,000.00
1.8 Add to Line Item No 10	\$23,500.00
1.9 Add 12"Directional Drill@ SR 15.(RFC#2)	\$34,760.00
1.10 Remove and Replace Asphalt Bike Path/sidewalk.(RFC#3)	\$85,825.00
1.11 Additional MOT Along Gator Blvd.(RFC#4)	\$24,000.00
1.12 Add testing along new pipeline route.(RFC#5)	\$5,216.86
1.13 Add 16"Directional Drill @ SR 15.(RFC#6)	\$39,600.00
1.14 Add 2" Long Services/w casing along Gator Blvd(RFC#7)	\$17,246.31
1.15 Add 2" Long Service @ Belle Glade Airport.(RFC#9)	\$3,500.00
1.16 Additional exploration of existing Utilities.(RFC#10)	\$25,622.66
1.17 Furnish and Install 12"x12" Tapping valve. (RFC# 13)	\$7,865.45
1.18 Furnish and Install Handicap ramps.(RFC#14)	\$8,400.00
1.19 Furnish and Install additional stripping.(RFC#15)	\$4,250.00

TOTAL (\$135,113.72)

NOT VALID UNTIL SIGNED BY BOTH OWNER AND ENGINEER. SIGNATURE OF THE CONTRACTOR INDICATES HIS CONTRACT HERewith INCLUDING ANY ADJUSTMENT IN THE CONTRACT SUM OR CONTRACT TIME, AND NO ADDITIONAL COST OR TIME INDICATED HEREIN WILL BE RELATED TO THIS CHANGE

The Original Contract Sum was .....	<u>\$2,149,199.00</u>
Net Change by previous Change Orders .....	<u>0.00</u>
The Contract Sum prior to this Change Order was .....	<u>\$2,149,199.00</u>
The Contract Sum will be decreased by this Change Order .....	<u>(\$135,113.72)</u>
The New Contract Sum indicating this Change Order will be ...	<u>\$2,014,085.28</u>
The Contract Time for will be increased by 0 days .....	<u>0 Days</u>
The Date of Substantial Compl. Including this Change Order:	<u>Sept 25, 2016</u>
The date of Final Compl.Including this Change Order:	<u>Oct 25, 2016</u>

SR 15 and Gator blvd water main Extension

Project No. WUD 13-052

District Number: 6

Contract No. R2015-1033

Change Order No. One (1)

-----  
EXECUTION OF THIS CHANGE ORDER ACKNOWLEDGES FINAL SETTLEMENT OF, AND  
RELEASES, ALL CLAIMS FOR COSTS AND TIME ASSOCIATED, DIRECTLY OR INDIRECTLY,  
WITH THE ABOVE STATED MODIFICATION (S), INCLUDING ALL CLAIMS FOR CUMULATIVE  
DELAYS OR DISRUPTIONS RESULTING FROM, CAUSED BY, OR INCIDENT TO SUCH  
MODIFICATION (S), AND INCLUDING ANY CLAIM THAT THE ABOVE STATED MODIFICATION  
CONSTITUTES, IN WHOLE OR PART, A CARDINAL CHANGE TO THE CONTRACT.  
-----

Palm Beach County

AKA Services Inc.

Palm Beach County

Joseph Tanacredi, P.E

**ENGINEER**

P.O. Box 16097

**Address**

WPB, Fl 33416

**CONTRACTOR**

15551 Okeechobee Blvd

**Address**

Loxahatchee, Fl 33470

Mary Lou Berger, Mayor

**OWNER:**

P.O. Box 16097

**Address**

WPB, Fl 33416

BY \_\_\_\_\_

BY \_\_\_\_\_

BY \_\_\_\_\_

DATE \_\_\_\_\_

DATE \_\_\_\_\_

DATE \_\_\_\_\_

Approved As Too Form and Legal Sufficiency

BY: \_\_\_\_\_

County Attorney

Attest: Sharon R. Bock, Clerk and Comptroller

BY: \_\_\_\_\_

Deputy Clerk

SR 15 and Gator blvd water main Extension

Project No. WUD 13-052

District Number: 6

Contract No. R2015-1033

Change Order No. One (1)

CHANGE ORDER CATEGORIZATION

☒ OWNER INITIATED

☒ QUANTITY OVERRUNS/UNDER-RUNS

☒ DIFFERING SITE CONDITIONS

☐ REQUEST BY ANOTHER AGENCY/OUTSIDE

☐ ZONING/CODE/ORDINANCE CHANGES

☐ A. REIMBURSABLE

☐ ERRORS/OMISSIONS/IN DESIGN

☐ B. NON-REIMBURSABLE

SR 15 and Gator blvd water main Extension

Project No. WUD 13-052

District Number: 6

Contract No. R2015-1033

Change Order No. One (1)

SCOPE OF WORK

- 1.1 Delete Line Item No 7, not used. (Owner Initiated)
- 1.2 Delete Line Item No 9, not used. (Owner Initiated)
- 1.3 Delete Line Item No 11, not used. (Owner Initiated)
- 1.4 Delete Line Item No 15, not used. (Owner Initiated)
- 1.5 Delete Line Item No 55, not used. (Owner Initiated)
- 1.6 Add to line Item No 6, additional quantity needed. (Quantity Overrun)
- 1.7 Add to line Item No 8, additional quantity needed. (Quantity Overrun)
- 1.8 Add to line Item No 10, additional quantity needed. (Quantity Overrun)
- 1.9 Add 12" diameter directional drill crossing Gator Blvd & SR 15 instead of open cut the road to avoid traffic interruption. (Owner Initiated)
- 1.10 The relocation of the water main to the south side of gator blvd required to remove the existing bike path/sidewalk to install the new water main. (Differ site Conditions)
- 1.11 The additional MOT is needed because of the relocation of the water main to the south side of Gator Blvd. The right of way is narrower on this side causing the contractor to impact traffic during installation. (Differ site conditions)
- 1.12 The additional testing was needed to test the soil on the new proposed pipeline route for any contaminates. This work was not included in the original contract. (Owner Initiated)
- 1.13 Add 16" diameter directional drill crossing SR 15 instead of open cut the road to avoid traffic interruption. (Owner Initiated)
- 1.14 Install 2" long water services with 3" casing to provide water to Belle Glade Airport property site facilities. (Differ Site condition)
- 1.15 Install 2" Long water service to Belle Glade Airport property site facility. Not in contract. (Differ site condition)
- 1.16 Additional exploratory investigation to locate existing utilities not shown on plans along the redesign route of water main. (Differ site condition)
- 1.17 Furnish and Install 12"x12" tapping sleeve and valve due at Gator Blvd and SR 15. Not in contract. (Differ site condition)
- 1.18 Furnish and install handicap ramps along Gator Blvd. Not in contract. (Differ site conditions)
- 1.19 Furnish and install additional stripping along Gator blvd. Not in contract (Differ site condition)



SR 15 and Gator blvd water main Extension

Project No. WUD 13-052

District Number: 6

Contract No. R2015-1033

Change Order No. One (1)

SUMMARY

<u>C.O. #</u>	<u>DESCRIPTION</u>	<u>ADDITIONS</u>	<u>(DELETIONS)</u>	<u>NET CHANGE</u>
1.1	Delete line Item No 7		176,400.00	(176,400.00)
1.2	Delete Line Item No 9		195,000.00	(195,000.00)
1.3	Delete Line Item No 11		40,000.00	(40,000.00)
1.4	Delete Line Item No 15		252,000.00	(252,000.00)
1.5	Delete Line Item No 55		13,500.00	(13,500.00)
1.6	Add to Line Item No 6	126,000.00		126,000.00
1.7	Add to Line Item No 8	136,000.00		136,000.00
1.8	Add to Line Item No 10	23,500.00		23,500.00
1.9	12" Directional Drill	34,760.00		34,760.00
1.10	Bike Path	85,825.00		85,825.00
1.11	MOT	24,000.00		24,000.00
1.12	Add testing	5,216.86		5,216.86
1.13	16" Directional Drill	39,600.00		39,600.00
1.14	3-2" Long Services	17,246.31		17,246.31
1.15	1-2" Long Service	3,500.00		3,500.00
1.16	exploration	25,622.66		25,622.66
1.17	12" Tap Sleeve & Valve	7,865.45		7,865.45
1.18	Handy cap ramps	8,400.00		8,400.00
1.19	stripping	4,250.00		4,250.00
		541,786.28	(676,900.00)	(135,113.72)



1.1 to 1.8

## SCHEDULE OF BID PRICES

Project No.: WUD 13-052

Project Name: SR-15 (Main St.) & Gator Blvd.; 16-inch and 12-inch Water Main  
Extension; City of Belle Glade  
City of Belle Glade

Item No.	Item Description	Quantity	Unit	Unit Price	Extended Price
1	Mobilization, Insurance, & Bonds	1	LS	\$ <u>50,000<sup>00</sup></u>	\$ <u>50,000.00</u>
2	Maintenance Of Traffic (MOT)	1	LS	\$ <u>15,000<sup>00</sup></u>	\$ <u>15,000.00</u>
3	Audio Video Documentation	17,080	LF	\$ <u>0.30</u>	\$ <u>5,124.00</u>
4	Pollution / Erosion Control	1	LS	\$ <u>21,000<sup>00</sup></u>	\$ <u>21,000.00</u>
5	8" C900 PVC Water Main	10	LF	\$ <u>100<sup>00</sup></u>	\$ <u>1,000.00</u>
ADD TO → (6)	12" C900 PVC Water Main	1,600	LF	\$ <u>30.00</u>	\$ <u>48,000.00</u>
DELETE → (7)	12" C900 PVC Water Main with Viton Gaskets	4,200	LF	\$ <u>42.00</u>	\$ <u>176,400.00</u>
ADD TO → (8)	16" C905 PVC Water Main	6,200	LF	\$ <u>40.00</u>	\$ <u>248,000.00</u>
DELETE → (9)	16" C905 PVC Water Main with Viton Gaskets	2,500	LF	\$ <u>78.00</u>	\$ <u>195,000.00</u>
ADD TO → (10)	12" DIP Water Main	600	LF	\$ <u>47.00</u>	\$ <u>28,200.00</u>
DELETE → (11)	12" DIP Water Main with Viton Gaskets	500	LF	\$ <u>80.00</u>	\$ <u>40,000.00</u>
12	16" DIP Water Main	310	LF	\$ <u>87.00</u>	\$ <u>26,970.00</u>
13	18" DR-11 HDD HDPE with 30" DR-11 Casing	360	LF	\$ <u>445.00</u>	\$ <u>160,200.00</u>
14	18" HDPE/MJ Adapter	2	EA	\$ <u>1,000<sup>00</sup></u>	\$ <u>2,000.00</u>
DELETE → (15)	Pipe Bursting 16" C905 Fusible PVC inside existing 12" PVC via pipe bursting	900	LF	\$ <u>280.00</u>	\$ <u>252,000.00</u>
16	Complete 16" Water Main Aerial Crossing (Addendum No 1)	1	LS	\$ <u>75,000<sup>00</sup></u>	\$ <u>75,000.00</u>
17	Fire Hydrant Assembly	14	EA	\$ <u>4,500<sup>00</sup></u>	\$ <u>63,000.00</u>
18	Remove Existing Fire Hydrant & Valve Box	2	EA	\$ <u>500<sup>00</sup></u>	\$ <u>1,000.00</u>
19	Remove Existing Valve Boxes	2	EA	\$ <u>250<sup>00</sup></u>	\$ <u>500.00</u>
20	1 1/2" SCH 80 PVC Water Service	2	EA <sup>1/4"</sup>	\$ <u>875<sup>00</sup></u>	\$ <u>1,750.00</u>
21	2" Corporation Stop with Double Saddle	1	EA	\$ <u>800<sup>00</sup></u>	\$ <u>800.00</u>
22	Connect Existing Water Service To New 12" Water Main	1	EA	\$ <u>500<sup>00</sup></u>	\$ <u>500.00</u>

1.1 - 1.8

23	Connect Existing Water Service To New 16" Water Main	1	EA	\$ <u>600<sup>00</sup></u>	\$ <u>600.00</u>
24	6" Gate Valve	3	EA	\$ <u>1,300<sup>00</sup></u>	\$ <u>3,900.00</u>
25	8" Gate Valve	8	EA	\$ <u>1,700<sup>00</sup></u>	\$ <u>13,600.00</u>
26	12" Gate Valve	1	EA	\$ <u>2,700<sup>00</sup></u>	\$ <u>2,700.00</u>
27	12" Butterfly Valve	15	EA	\$ <u>2,400<sup>00</sup></u>	\$ <u>36,000.00</u>
28	16" Butterfly Valve	10	EA	\$ <u>3,300<sup>00</sup></u>	\$ <u>33,000.00</u>
29	Air Release Valve with Manhole	2	EA	\$ <u>6,300<sup>00</sup></u>	\$ <u>12,600.00</u>
30	Water Main Fittings	18	TON	\$ <u>8,000<sup>00</sup></u>	\$ <u>144,000.00</u>
31	8" Line Stop	1	EA	\$ <u>4,500<sup>00</sup></u>	\$ <u>4,500.00</u>
32	12" Line Stop	2	EA	\$ <u>6,500<sup>00</sup></u>	\$ <u>13,000.00</u>
33	Connect To Existing 12" Gate Valve	2	EA	\$ <u>1,500<sup>00</sup></u>	\$ <u>3,000.00</u>
34	Connect To Existing 6" Water Main	2	EA	\$ <u>500<sup>00</sup></u>	\$ <u>1,000.00</u>
35	Connect To Existing 8" Water Main	3	EA	\$ <u>750<sup>00</sup></u>	\$ <u>2,250.00</u>
36	Connect to Existing 12" Water Main	5	EA	\$ <u>1,500<sup>00</sup></u>	\$ <u>7,500.00</u>
37	Sample Points (Addendum No 1)	45 22	EA	\$ <u>250<sup>00</sup></u>	\$ <u>5,500.00</u>
38	Bollards	2	EA	\$ <u>275<sup>00</sup></u>	\$ <u>550.00</u>
39	Asphalt Road Crossing Cut, Curb, & Landscape Median Restoration	150	SY	\$ <u>35<sup>00</sup></u>	\$ <u>5,250.00</u>
40	Road Crossing Cut & Restoration Including Milling and Overlay	2,000	SY	\$ <u>55<sup>00</sup></u>	\$ <u>110,000.00</u>
41	Road Crossing Cut & Restoration (No Milling or Overlay)	400	SY	\$ <u>35<sup>00</sup></u>	\$ <u>14,000.00</u>
42	Restore Dirt Road	100	SY	\$ <u>25<sup>00</sup></u>	\$ <u>2,500.00</u>
43	Asphalt Driveway Crossing & Restoration	840	SY	\$ <u>33<sup>00</sup></u>	\$ <u>27,720.00</u>
44	Cut & Cap Existing 8" Water Main	1	EA	\$ <u>1,200<sup>00</sup></u>	\$ <u>1,200.00</u>
45	Cut & Cap Existing 12" Water Main	1	EA	\$ <u>1,350<sup>00</sup></u>	\$ <u>1,350.00</u>
46	Remove Exposed 12" Water Main and Valve	1	LS	\$ <u>600<sup>00</sup></u>	\$ <u>600.00</u>
47	Remove Existing 12" Water Main Pipe	1	LS	\$ <u>600<sup>00</sup></u>	\$ <u>600.00</u>
48	Remove Existing 12" 90 Degree Bend	1	LS	\$ <u>1,200<sup>00</sup></u>	\$ <u>1,200.00</u>
49	Abandon Existing 8" Water Main	4,665	LF	\$ <u>2<sup>00</sup></u>	\$ <u>9,330.00</u>

50	Abandon Existing 12" Water Main	12,235	LF	\$ <u>3<sup>00</sup></u>	\$ <u>36,705.00</u>
51	Prune Trees & Install Root Barrier	1	LS	\$ <u>1,200<sup>00</sup></u>	\$ <u>1,200.00</u>
52	Remove and Replace Guy Wire	1	LS	\$ <u>1,700<sup>00</sup></u>	\$ <u>1,700.00</u>
53	Remove and Replace Signs	1	LS	\$ <u>800<sup>00</sup></u>	\$ <u>800.00</u>
54	Remove and Replace Guardrail	1	LS	\$ <u>10,000<sup>00</sup></u>	\$ <u>10,000.00</u>
55	Remove and Dispose Contaminated Soils	100	CY	\$ <u>135<sup>00</sup></u>	\$ <u>13,500.00</u>
56	Demucking with Imported Clean Fill	9,000	CY	\$ <u>20<sup>00</sup></u>	\$ <u>180,000.00</u>
57	Poly-Wrap 4"-8" Ductile Iron Pipe and Fittings	400	LF	\$ <u>3<sup>00</sup></u>	\$ <u>1,200.00</u>
58	Poly-Wrap 10"-16" Ductile Iron Pipe and Fittings	2,000	LF	\$ <u>3<sup>00</sup></u>	\$ <u>6,000.00</u>
59	Cut & Cap Existing 16" Water Main (Addendum No 1)	2	EA	\$ <u>2,500<sup>00</sup></u>	\$ <u>5,000.00</u>
60	Canal Bank Stabilization (Addendum No 1)	30	LF	\$ <u>60<sup>00</sup></u>	\$ <u>1,800.00</u>
61	Concrete Sidewalk Restoration (Addendum No 1)	160	SY	\$ <u>50<sup>00</sup></u>	\$ <u>8,000.00</u>
62	Remove and Dispose AC Pipe (8"-12") (Addendum No 1)	100	LF	\$ <u>39<sup>00</sup></u>	\$ <u>3,900.00</u>
63	Remove Existing 12" Aerial Crossing (Addendum No 1)	1	LS	\$ <u>5,500<sup>00</sup></u>	\$ <u>5,500.00</u>
64	Remove Existing 8" Water Main Pipe (Addendum No 1)	50	LF	\$ <u>100<sup>00</sup></u>	\$ <u>5,000.00</u>

TOTAL BID= \$ 2,149,199.00

TOTAL BASE BID IN WORDS: TWO MILLION ONE HUNDRED FORTY NINE  
THOUSAND ONE HUNDRED NINETY NINE DOLLARS, AND  
ZERO CENTS

(The Total Bid Price is to be written in numerical figures above. In case of discrepancies or errors, the unit price shown for each bid item shall govern and the corrected Total Bid Price shall be calculated as such.)

(Total Bid Price are to be shown in both words and figures. In case of discrepancies, the amount shown in words will govern.)

The Bidder agrees to furnish and pay for all materials necessary to complete the project which includes but is not limited to furnished materials, labor supervision, equipment, supplies, fees, expertise, and services necessary to fully complete all work in accordance with all requirements of the Construction Plans, the Contract Documents and in accordance with all applicable codes and governing regulations, within the time limit specified. Bidder assumes all costs, delays, and risks associated with all conditions or occurrences which cause or might cause an increase in Bidder's cost to complete the Work or which cause or might cause delays in Bidder's prosecution of the Work. Bid price shall include all adjustments to pipeline alignment, within 6' horizontal and 3' vertical from locations shown on construction plans. Adjustments exceeding the above dimensions caused by unknown and reasonably unforeseeable subsurface conditions or conflicts, which cause any material deviation in the alignment of a pipeline location, shall be considered for an allowance or change condition for additional materials, labor and equipment.

## 1. 9

Page 1 of 2





[illegible][illegible]

# REQUEST FOR CHANGE ORDER

<b>Project:</b>	SR 15 and Gator Boulevard WM Extension	<b>RFCO #</b>	4
<b>Owner:</b>	PBCWUD		
<b>Engineer:</b>	Joe Tanacredi		
<b>Contractor:</b>	AKA Services, Inc.		
CONTINUATION SHEET USED?    YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>			
Referenced Contract Documents : Contract Drawings			
<b>Request for Change Order Information</b>			
	Change requested to Contract for Additional MOT required by relocation of 12" Water Main from North ROW of Gator Boulevard to South ROW of Gator Boulevard to avoid installation of mains in areas of contaminated soils. Cost breakdown sheet attached:		
	Total Additional Cost Per Attached:                      \$ 24,000.00		
<b>RFCO BY:</b>		<b>RFCO Issue Date:</b>	
Mike Heltzler		03/03/2016	
<b>Response :</b>			
<b>Response By / Date:</b>		<b>Position:</b>	
Issued To:		Issued for Information:	
		Mario Basile, AKA Services, Inc.	

Additional Cost for MOT to effect Lane Closure required to Install 12" WM on south side of Gator Boulevard

[illegible]

## REQUEST FOR CHANGE ORDER

<b>Project:</b>	SR 15 and Gator Boulevard WM Extension	<b>RFCO #</b>	5
<b>Owner:</b>	PBCWUD		
<b>Engineer:</b>	Joe Tanacredi		
<b>Contractor:</b>	AKA Services, Inc.		
CONTINUATION SHEET USED?   YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>			
Referenced Contract Documents : Contract Drawings			
Request for Change Order Information			
Change requested to Contract for Additional Soil Testing and Reports required for relocation of 16" and 12" Water Mains per direction of PBCWUD			
Total Additional Cost Per Attached: \$ 5,216.86			
RFCO BY: Mike Heitzler		RFCO Issue Date: 03/03/2016	
Response :			
Response By / Date:		Position:	
Issued To:		Issued for Information:	
		Mario Basile, AKA Services, Inc.	

DESCRIPTION:

Relocation of Water Mains

0

Item Description	Quantity	Labor	Equipment	Materials	Subcontract Work	Total
PBCWUD Additional Work	1 LS	1,544.40	\$ 602.52	\$ -	\$ 2,923.75	\$ 5,070.67
Totals		\$ 1,544.40	\$ 602.52	\$ -	\$ 2,923.75	\$ 5,070.67
Total Work AKA Services Inc.						\$ 2,146.92
Contractor's Fee Per Contract Section - 0%						\$ -
Subtotal "A"						\$ 2,146.92
Total Work Subcontractors						\$ 2,923.75
Contractor's Fee Per Contract Section - 5.0%						\$ 146.19
Subtotal "B"						\$ 3,069.94
Total Cost A+B						\$ 5,216.86
Bond Cost 0.00%						\$ -
<b>Total Change Order Amount</b>						<b>\$ 5,216.86</b>
<b>Total Change Order Day(s)</b>						



**DESCRIPTION:****Relocation of Water Mains Exploration****Labor**

Description	Quantity	Hourly Rate	Extension
Superintendent	12 hr @	\$ 55.00	\$ 660.00
Foreman	0 hr @	\$ 38.50	\$ -
Operator	12 hr @	\$ 23.00	\$ 276.00
Driver/Dump	0 hr @	\$ 15.00	\$ -
Driver/Lowboy	0 hr @	\$ 15.00	\$ -
Pipelayer	0 hr @	\$ 15.00	\$ -
Tailman	0 hr @	\$ 14.00	\$ -
Hillman	0 hr @	\$ 12.00	\$ -
Laborer	12 hr @	\$ 12.00	\$ 144.00

Subtotal \$ 1,080.00

Labor Burden @ 30.00% \$ 324.00

Allowable Markup @ 10.00% \$ 140.40

Total Labor \$ 1,544.40

**Equipment**

Description	Quantity	Hourly Rate	Operating	Extension
Pick-up - Superint.	12 hr @	\$ 8.00	\$ 6.04	\$ 168.48
Pick-up - Foreman	0 hr @	\$ 8.00	\$ 6.04	\$ -
Dump - 18 CY	0 hr @	\$ 46.00	\$ 22.32	\$ -
Lowboy	0 hr @	\$ 68.00	\$ 22.32	\$ -
Cat 613c-II Water Wagon	0 hr @	\$ 38.00	\$ 11.18	\$ -
IHC 50 Broom Tractor	0 hr @	\$ 29.00	\$ 7.17	\$ -
Cat 235D Track Hoe	0 hr @	\$ 138.00	\$ 34.02	\$ -
Komatsu PC300 HD-6 Track Hoe	0 hr @	\$ 126.00	\$ 29.87	\$ -
Komatsu PC228 Track Hoe	0 hr @	\$ 108.00	\$ 26.99	\$ -
Komatsu PC138 Track Hoe	0 hr @	\$ 85.00	\$ 26.99	\$ -
WB 140 RT Backhoe Combo	12 hr @	\$ 29.00	\$ 7.17	\$ 434.04
Komatsu WA320-Loader	0 hr @	\$ 53.00	\$ 17.85	\$ -
Komatsu WA250-Loader	0 hr @	\$ 42.00	\$ 12.45	\$ -
Komatsu WA95-Loader	0 hr @	\$ 36.00	\$ 9.77	\$ -
IT 28G Loader	0 hr @	\$ 42.00	\$ 12.45	\$ -
Cat 966 Loader	0 hr @	\$ 49.00	\$ 15.33	\$ -
Bobcat 450	0 hr @	\$ 11.00	\$ 2.78	\$ -
Cat 12G Grader	0 hr @	\$ 18.00	\$ 14.12	\$ -
Cat D-3 -III Dozer	0 hr @	\$ 36.00	\$ 9.77	\$ -
Cat D-5 -II Dozer	0 hr @	\$ 43.00	\$ 11.45	\$ -
SV 210 Roller	0 hr @	\$ 62.00	\$ 8.82	\$ -
SD 40D Roller	0 hr @	\$ 53.00	\$ 5.30	\$ -
DD 22 Roller	0 hr @	\$ 29.00	\$ 7.17	\$ -

Bros Mixer	0	hr @ \$	187.00	\$	64.42	\$	-
Skid Steer	0	hr @ \$	38.00	\$	11.18	\$	-
Asphalt Zipper	0	hr @ \$	38.00	\$	11.18	\$	-
Jet Pump	0	hr @ \$	24.00	\$	13.44	\$	-
Wellpoint Pump	0	hr @ \$	33.00	\$	13.44	\$	-
6" Hyd. Pump & Hose	0	hr @ \$	24.00	\$	13.44	\$	-
3" Diaph. Pump & Hoses	0	hr @ \$	6.25	\$	0.85	\$	-
14" Cut-off Saw	0	hr @ \$	3.15	\$	0.95	\$	-
Light Tower 20'	0	hr @ \$	5.85	\$	1.05	\$	-
Road Plates	0	hr @ \$	2.60	\$	-	\$	-
Small/Misc. Tools	0	hr @ \$	10.00	\$	-	\$	-
Milling Machine	0	hr @ \$	68.00	\$	-	\$	-
Street Saw	0	hr @ \$	14.00	\$	-	\$	-
Total Equipment						\$	602.52

### Material

Description	Quantity	Unit Cost	Extension
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -
	@		\$ -

Subtotal	\$	-
6% Sales Tax	\$	-
10% Markup	\$	-
Total Material	\$	-

### Subcontract Work

Description	Quantity	Unit Cost	Extension
Testing & Sample Report	1 LS @	\$ 2,923.75	\$ 2,923.75
Total Subcontract Work			\$ 2,923.75

1.13

## Request for Change

Project:	SR 15 (Main Street) and Gator Boulevard WM Extension	RFC No. :	6
Owner:	PBCWUD		
Engineer:	Joe Tanacredi		
Contractor:	AKA Services, Inc.		
CONTINUATION SHEET USED? YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>			
Referenced Contract Documents : Contract Specifications			
Request for Change:			
Install 16" HDPE via directional bore in lieu of open cut road crossings as shown on Sheet P-5 of the Contract Drawings @ the following cost.			
180 LF (Approx.) 16" HDPE @ \$ 220.00 \$ 39,600.00			
Credits to be taken @ Contract Unit Prices for Items not installed including:			
10. 16" DIP Water Main			
11. 16" DIP Water Main w/Viton Gaskets			
39. Asphalt Road Crossing Cut, Curb and Landscape Median Restoration			
40. Asphalt Road Cut & Restoration Including Milling and Overlay			
41. Road Crossing Cut & Restoration (No Milling or Overlay)			
RFI Originator: Mike Heitzler RFC Issue Date: 05/03/16			
Response :			
Response By / Date:		Position:	
Issued To:		Issued for Information:	
		Mario Basile, AKA Services, Inc.	

## Request for Change

[illegible]



## Request for Change

[illegible]

1.16

# REQUEST FOR CHANGE ORDER

<b>Project:</b>	SR 15 and Gator Boulevard WM Extension		<b>RFCO #</b>	10
<b>Owner:</b>	PBCWUD			
<b>Engineer:</b>	Joe Tanacredi			
<b>Contractor:</b>	AKA Services, Inc.			
CONTINUATION SHEET USED?    YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>				
Referenced Contract Documents : Contract Drawings				
<b>Request for Change Order Information</b>				
	Change requested to Contract for additional exploration and locating of existing utilities and determination of soil conditions required by relocation of 16" WM from the east side of SR 15 to the west side of SR 15.			
	Pipe Crew and Equipment	7 days @ \$ 3,660.38	\$ 25,622.66	
<b>RFCO BY:</b>	Mike Heitzler	<b>RFCO Issue Date:</b>	05/03/2016	
<b>Response :</b>				
<b>Response By / Date:</b>			<b>Position:</b>	
<b>Issued To:</b>		<b>Issued for Information:</b>		
		Mario Basile, AKA Services, Inc.		

## DESCRIPTION:

Relocation of Water Mains

0

Item Description	Quantity	Labor	Equipment	Materials	Subcontract Work	Total
------------------	----------	-------	-----------	-----------	------------------	-------

PBCWUD Additional Work	1 LS	1,307.02	\$ 1,875.92	\$ -	\$ -	\$ 3,182.94
Totals		\$ 1,307.02	\$ 1,875.92	\$ -	\$ -	\$ 3,182.94

Total Work AKA Services Inc.						\$ 3,182.94
Contractor's Fee Per Contract Section -	15%					\$ 477.44
Subtotal "A"						\$ 3,660.38

Total Work Subcontractors						\$ -
Contractor's Fee Per Contract Section -	0.00%					\$ -
Subtotal "B"						\$ -

Total Cost A+B						\$ 3,660.38
Bond Cost	0.00%					\$ -

<b>Total Change Order Amount \$ 3,660.38</b>
--

<b>Total Change Order Day(s)</b>
----------------------------------

## DESCRIPTION:

## Locating Required for 16" WM Relocation

Labor

Description	Quantity	Hourly Rate	Extension
Superintendent	2 hr @ \$	55.00	\$ 110.00
Foreman	8 hr @ \$	38.50	\$ 308.00
Operator	8 hr @ \$	23.00	\$ 184.00
Driver/Dump	0 hr @ \$	15.00	\$ -
Driver/Lowboy	0 hr @ \$	15.00	\$ -
Pipelayer	8 hr @ \$	15.00	\$ 120.00
Tailman	0 hr @ \$	14.00	\$ -
Hillman	0 hr @ \$	12.00	\$ -
Laborer	16 hr @ \$	12.00	\$ 192.00
Subtotal			\$ 914.00
Labor Burden @ 30.00%			\$ 274.20
Allowable Markup @ 10.00%			\$ 118.82
Total Labor			\$ 1,307.02

Equipment

Description	Quantity	Hourly Rate	Operating	Extension
Pick-up - Superint.	2 hr @ \$	8.00	\$ 6.04	\$ 28.08
Pick-up - Foreman	8 hr @ \$	8.00	\$ 6.04	\$ 112.32
Dump - 18 CY	0 hr @ \$	46.00	\$ 22.32	\$ -
Lowboy	0 hr @ \$	68.00	\$ 22.32	\$ -
Cat 613c-II Water Wagon	0 hr @ \$	38.00	\$ 11.18	\$ -
IHC 50 Broom Tractor	0 hr @ \$	29.00	\$ 7.17	\$ -
Cat 235D Track Hoe	0 hr @ \$	138.00	\$ 34.02	\$ -
Komatsu PC300 HD-6 Track Hoe	0 hr @ \$	126.00	\$ 29.87	\$ -
Komatsu PC228 Track Hoe	0 hr @ \$	108.00	\$ 26.99	\$ -
Komatsu PC138 Track Hoe	8 hr @ \$	85.00	\$ 26.99	\$ 895.92
WB 140 RT Backhoe Combo	0 hr @ \$	29.00	\$ 7.17	\$ -
Komatsu WA320-Loader	0 hr @ \$	53.00	\$ 17.85	\$ -
Komatsu WA250-Loader	0 hr @ \$	42.00	\$ 12.45	\$ -
Komatsu WA95-Loader	8 hr @ \$	36.00	\$ 9.77	\$ 366.16
IT 28G Loader	0 hr @ \$	42.00	\$ 12.45	\$ -
Cat 966 Loader	0 hr @ \$	49.00	\$ 15.33	\$ -
Bobcat 450	0 hr @ \$	11.00	\$ 2.78	\$ -
Cat 12G Grader	0 hr @ \$	18.00	\$ 14.12	\$ -
Cat D-3 -III Dozer	0 hr @ \$	36.00	\$ 9.77	\$ -
Cat D-5 -II Dozer	0 hr @ \$	43.00	\$ 11.45	\$ -
SV 210 Roller	0 hr @ \$	62.00	\$ 8.82	\$ -
SD 40D Roller	0 hr @ \$	53.00	\$ 5.30	\$ -
DD 22 Roller	0 hr @ \$	29.00	\$ 7.17	\$ -

Bros Mixer	0	hr @ \$	187.00	\$	64.42	\$	-
Skid Steer	8	hr @ \$	38.00	\$	11.18	\$	393.44
Asphalt Zipper	0	hr @ \$	38.00	\$	11.18	\$	-
Jet Pump	0	hr @ \$	24.00	\$	13.44	\$	-
Wellpoint Pump	0	hr @ \$	33.00	\$	13.44	\$	-
6" Hyd. Pump & Hose	0	hr @ \$	24.00	\$	13.44	\$	-
3" Diaph. Pump & Hoses	0	hr @ \$	6.25	\$	0.85	\$	-
14" Cut-off Saw	0	hr @ \$	3.15	\$	0.95	\$	-
Light Tower 20'	0	hr @ \$	5.85	\$	1.05	\$	-
Road Plates	0	hr @ \$	2.60	\$	-	\$	-
Small/Misc. Tools	8	hr @ \$	10.00	\$	-	\$	80.00
Milling Machine	0	hr @ \$	68.00	\$	-	\$	-
Street Saw	0	hr @ \$	14.00	\$	-	\$	-
Total Equipment						\$	1,875.92

### Material

Description	Quantity	Unit Cost	Extension
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-
	@	\$	-

Subtotal	\$	-
6% Sales Tax	\$	-
10% Markup	\$	-
Total Material	\$	-



### Subcontract Work

Description	Quantity	Unit Cost	Extension
LS @	\$	-	\$ -
Total Subcontract Work		\$	-

# REQUEST FOR CHANGE ORDER

<b>Project:</b>	SR 15 and Gator Boulevard WM Extension	<b>RFCO #</b>	13
<b>Owner:</b>	PBCWUD		
<b>Engineer:</b>	Joe Tanacredi		
<b>Contractor:</b>	AKA Services, Inc.		
CONTINUATION SHEET USED?    YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>			
<b>Referenced Contract Documents : Contract Drawings</b>			
<b>Request for Change Order Information</b>			
	Cost of 12" X 12" Tapping Sleeve and Valve Installation required due to Plan changes to relocate 12" WM crossing of Gator Boulevard @ SR 15 Intersection.  12" X 12" Tapping Sleeve & Valve      1 EA.   @   \$ 7,865.45      \$ 7,865.45		
<b>RFCO BY:</b>	Mike Heitzler	<b>RFCO Issue Date:</b>	
<b>Response :</b>			
<b>Response By / Date:</b>		<b>Position:</b>	
<b>Issued To:</b>		<b>Issued for Information:</b>	
		Mario Basile, AKA Services, Inc.	

## DESCRIPTION:

12" TS &amp; V

Item Description	Quantity	Labor	Equipment	Materials	Subcontract Work	Total
This Claim	1 LS	574.56	\$ 698.28	\$ 4,836.25	\$ 800.00	\$ 6,909.09
	Totals	\$ 574.56	\$ 698.28	\$ 4,836.25	\$ 800.00	\$ 6,909.09
Total Work AKA Services Inc.						\$ 6,109.09
Contractor's Fee Per Contract Section - 15%						\$ 916.36
Subtotal "A"						\$ 7,025.45
Total Work Subcontractors						\$ 800.00
Contractor's Fee Per Contract Section - 5.0%						\$ 40.00
Subtotal "B"						\$ 840.00
Total Cost A+B						\$ 7,865.45
Bond Cost 0.00%						\$ -
<b>Total Change Order Amount</b>						<b>\$ 7,865.45</b>
<b>Total Change Order Day(s)</b>						<b>-</b>

**DESCRIPTION:****12" TS & V****Labor**

Description	Quantity		Hourly Rate	Extension	
Superintendence	0	hr	@ \$ 55.00	\$ -	
Foreman	4	hr	@ \$ 40.00	\$ 160.00	
Operator	4	hr	@ \$ 23.00	\$ 92.00	10.000%
Driver/Dump	0	hr	@ \$ 18.00	\$ -	0.000%
Driver/Lowboy	0	hr	@ \$ 15.00	\$ -	
Pipelayer	4	hr	@ \$ 18.00	\$ 72.00	0.000%
Tailman	0	hr	@ \$ 14.00	\$ -	
Hillman	0	hr	@ \$ 12.00	\$ -	
Laborer	8	hr	@ \$ 12.00	\$ 96.00	17.000%
Subtotal				\$ 420.00	3.800%
0 Labor Burden @ 36.80%				\$ 154.56	2.200%
Total Labor				\$ 574.56	3.800%
					36.800%

**Equipment**

Description	Quantity		Hourly Rate	Operating	Extension
Pick-up - Superint.	0	hr	@ \$ 5.00	\$ 6.04	\$ -
Pick-up - Foreman	4	hr	@ \$ 5.00	\$ 6.04	\$ 44.16
Dump - 18 CY	0	hr	@ \$ 26.00	\$ 22.32	\$ -
Lowboy	0	hr	@ \$ 68.00	\$ 22.32	\$ -
PC 35 MR3 Mini excavator	0	hr	@ \$ 45.00	\$ 11.18	\$ -
CX 50B Mini Excavator	0	hr	@ \$ 45.00	\$ 7.17	\$ -
Cat 235D Track Hoe	0	hr	@ \$ 138.00	\$ 34.02	\$ -
Komatsu PC300 HD-6 Track Hoe	0	hr	@ \$ 63.00	\$ 29.87	\$ -
Komatsu PC228 Track Hoe	0	hr	@ \$ 108.00	\$ 26.99	\$ -
Komatsu PC138 Track Hoe	4	hr	@ \$ 85.00	\$ 26.99	\$ 447.96
WB 140 RT Backhoe Combo	0	hr	@ \$ 29.00	\$ 7.17	\$ -
Volvo L90G - Loader	0	hr	@ \$ 75.00	\$ 17.85	\$ -
Volvo L70G - Loader	0	hr	@ \$ 70.00	\$ 12.45	\$ -
Komatsu WA95-Loader	0	hr	@ \$ 36.00	\$ 9.77	\$ -
IT 28G Loader	0	hr	@ \$ 42.00	\$ 12.45	\$ -
Case loader 321-E	0	hr	@ \$ 49.00	\$ 15.33	\$ -
Case Mini track loader	0	hr	@ \$ 40.00	\$ 2.78	\$ -
Komatsu mini track loader	0	hr	@ \$ 40.00	\$ 14.12	\$ -
Cat D-3 -III Dozer	0	hr	@ \$ 18.00	\$ 9.77	\$ -
Cat D-5 -II Dozer	0	hr	@ \$ 43.00	\$ 11.45	\$ -
SV 210 Roller	0	hr	@ \$ 62.00	\$ 8.82	\$ -
SD 40D Roller	0	hr	@ \$ 53.00	\$ 5.30	\$ -
DD 22 Roller	0	hr	@ \$ 15.00	\$ 7.17	\$ -

Bros Mixer	0	hr	@	\$	187.00	\$	64.42	\$	-
Sweeper	0	hr	@	\$	25.00	\$	11.18	\$	-
Asphalt Zipper	0	hr	@	\$	38.00	\$	11.18	\$	-
Jet Pump	0	hr	@	\$	24.00	\$	13.44	\$	-
Wellpoint Pump	0	hr	@	\$	33.00	\$	13.44	\$	-
6" Hyd. Pump & Hose	4	hr	@	\$	24.00	\$	13.44	\$	149.76
3" Diaph. Pump & Hoses	0	hr	@	\$	6.25	\$	0.85	\$	-
14" Cut-off Saw	4	hr	@	\$	3.15	\$	0.95	\$	16.40
Light Tower 20'	0	hr	@	\$	5.85	\$	1.05	\$	-
Road Plates	0	hr	@	\$	2.60	\$	-	\$	-
Small/Misc. Tools	4	hr	@	\$	10.00	\$	-	\$	40.00
Misc.	0	hr	@	\$	-	\$	-	\$	-
Total Equipment									\$ 698.28

### Material

Description	Quantity		Unit Cost	Extension
12" TS & V	1	EA	@ \$ 4,562.50	\$ 4,562.50
			@ \$ -	\$ -
			@ \$ -	\$ -
			@ \$ -	\$ -
			@ \$ -	\$ -
			@ \$ -	\$ -
			@ \$ -	\$ -
Subtotal				\$ 4,562.50
6% Sales Tax				\$ 273.75
Total Material				\$ 4,836.25

### Subcontract Work

Description	Quantity		Unit Cost	Extension
12' Test & Tap	1	EA	@ \$ 800.00	\$ 800.00
Total Subcontract Work				\$ 800.00

# REQUEST FOR CHANGE ORDER

<b>Project:</b>	SR 15 and Gator Boulevard WM Extension		<b>RFCO #</b>	14				
<b>Owner:</b>	PBCWUD							
<b>Engineer:</b>	Joe Tanacredi							
<b>Contractor:</b>	AKA Services, Inc.							
CONTINUATION SHEET USED?    YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>								
<b>Referenced Contract Documents : Contract Drawings</b>								
<b>Request for Change Order Information</b>								
	Change requested to Contract for Handicap Truncated Dome installation required by relocation of 16" Water Main from East ROW of SR 15 to West ROW of SR 15 and for 12" Water Main relocation from North ROW of Gator Blvd. to South ROW of Gator Boulevard to avoid installation of mains in areas of contaminated soils.							
	F & I Handicap Truncated Domes      8 Ea. @ \$ 1,050.00      \$ 8,400.00							
<table border="1" style="width:100%"> <tr> <td style="width:20%"><b>RFCO BY:</b></td> <td style="width:40%">Mike Heitzler</td> <td style="width:20%"><b>RFCO Issue Date:</b></td> <td style="width:20%">05/16/2016</td> </tr> </table>					<b>RFCO BY:</b>	Mike Heitzler	<b>RFCO Issue Date:</b>	05/16/2016
<b>RFCO BY:</b>	Mike Heitzler	<b>RFCO Issue Date:</b>	05/16/2016					
<b>Response :</b>								
<b>Response By / Date:</b>		<b>Position:</b>						
<b>Issued To:</b>		<b>Issued for Information:</b>						
		Mario Basile, AKA Services, Inc.						



1.19

# REQUEST FOR CHANGE ORDER

<b>Project:</b>	SR 15 and Gator Boulevard WM Extension	<b>RFCO #</b>	15
<b>Owner:</b>	PBCWUD		
<b>Engineer:</b>	Joe Tanacredi		
<b>Contractor:</b>	AKA Services, Inc.		
CONTINUATION SHEET USED?    YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>			
<b>Referenced Contract Documents : Contract Drawings</b>			
<b>Request for Change Order Information</b>			
	Change requested to Contract for Roadway Striping required by relocation of 16" Water Main from East ROW of SR 15 to West ROW of SR 15 and from North ROW of Gator Boulevard to South ROW of Gator Boulevard to avoid installation of mains in areas of contaminated soils.		
	Roadway Striping	1 LS	\$ 4250.00
RFCO BY: Mike Heitzler      RFCO Issue Date: 05/18/2016			
<b>Response :</b>			
Response By / Date:		Position:	
Issued To:		Issued for Information:	
		Mario Basile, AKA Services, Inc.	



## SUPPLEMENT ADDITIONS/DELETIONS SUMMARY

PROJECT:	SR 15 and Gator Blvd Water Main Extension				<u>APPROVAL LIMITS:</u>						
CONTRACTOR:	AKA Services, Inc				DEPARTMENT HEAD		CONTRACT REVIEW COMMITTEE		DEPARTMENT HEAD PLUS CONTRACT REVIEW COMMITTEE		
PROJECT NO.:	13-052										
RESOLUTION:	R20015-1033				(Amount)	(Days)	(Amount)	(Days)	(Amount)	(Days)	
DATE APPROVED:	08/18/15				INDIVIDUAL C.O.	\$50,000.00	30 Days	\$100,000.00	90 Days	\$0	0 Days
CONTRACT AMOUNT:	\$2,149,199.00				CUMMULATIVE C.O.	\$50,000.00	30 Days	\$100,000.00	90 Days	\$200,000.00	120 Days
			DEPARTMENT HEAD		CONTRACT REVIEW COMMITTEE		TOTAL DEPT. HEAD & CONTRACT REVIEW COMM.		BOARD OF COUNTY COMMISSIONERS		
	DATE	NET	(ADDS PLUS DEDUCTS)		(ADDS PLUS DEDUCTS)		(ADDS PLUS DEDUCTS)		(ADDS PLUS DEDUCTS)		
Supple	APPROVED	CHANGE	AMOUNT	DAYS	AMOUNT	DAYS	AMOUNT	DAYS	AMOUNT	DAYS	TOTALS
001	Pending	(135,113.72)	0	0	0	0	0	0	(135,113.72)	0	(135,113.72)
</											

Notes:

1. Net Change reflects the net amount of additions plus deductions.
2. Adds plus Deducts reflects the net value of unrelated changes for use in determining the approval authority for the Change Order.
3. Liquidated Damages = \$500 (Prior to Substantial Completion) and = \$500 (After Substantial Completion).

SCHEDULE 1

PARTICIPATION BY SBE/WBE SUBCONTRACTORS

PROJECT NAME: SR 15 and Gator Blvd Water Main Extension 13-052

NAME OF PRIME CONTRACTOR: AKA Services Inc Change Order NO. 1

CONTACT PERSON: \_\_\_\_\_ PHONE NO: \_\_\_\_\_ FAX NO. \_\_\_\_\_

Change Order No: 1 DEPARTMENT: Water Utilities

Name, Address and Phone Number of M/WBE	Type of Work To Be Performed	Subcontract Amount			
		Black	Hispanic	Women	Other (Please Specify)
1.		_____	_____	_____	_____
2.		_____	_____	_____	_____
3.		_____	_____	_____	_____
4.		_____	_____	_____	_____
5.		_____	_____	_____	_____
6.		_____	_____	_____	_____
7.		_____	_____	_____	_____
8.		_____	_____	_____	_____
9.		_____	_____	_____	_____
10.		_____	_____	_____	_____
Totals		<u>\$ 0.00</u>	<u>\$ 0.00</u>	<u>\$ 0.00</u>	<u>\$ 0.00</u>

Original Contract Amount	<u>\$2,149,199.00</u>	Original Participation	<u>338,864.00</u>	Percent Participation	<u>15.76</u>
Adjusted Contract Amount	<u>\$2,014,085.28</u>	Adjusted Participation	<u>338,864.00</u>	Adjusted Percent	<u>16.82</u>