PALM BEACH COUNTY BOARD OF COUNTY COMMISSIONERS <u>AGENDA ITEM SUMMARY</u>

Meeting Date:	May 1, 2018	[X] Consent [] Ordinance	[] Regular [] Public Hearing
Department:	Engineering & P	ublic Works	
Submitted By:	Engineering & P	ublic Works	
Submitted For:	Traffic Division		

I. EXECUTIVE BRIEF

Motion and Title: Staff recommends motion to approve: A work order in the amount of \$250,002.60 to construct a mast arm traffic signal to replace the existing span wire structure at the intersection of Lantana Road and Bentbrook Boulevard/Gateview Terrace, Palm Beach County (County) Intersection ID Number 40015 (Project), utilizing the County's amended annual traffic signal contract R2018-0208 with Gerelco Traffic Controls, Inc. (Gerelco).

SUMMARY: Approval of this work order will allow Gerelco to construct the project. Per County PPM CW-F-050, this work order exceeds the threshold relating to staff approvals of work orders to annual contracts, thus requiring approval from the Board of County Commissioners (BCC). Prior to this work order, over \$631,461.70 of Gerelco's \$4,000,000 contract has been spent or encumbered. Gerelco is a Port St. Lucie based company with an office in Palm Beach County. The Small Business Enterprise (SBE) goal for all contracts is 15%. Gerelco's SBE participation proposed for this work order is 35.9%. Approval of this work order will result in a cumulative SBE participation of 17.7% for all work orders issued under the contract. District 3 (LBH)

Background and Justification: On March 13, 2018, the BCC approved an amended annual traffic signal contract R2018-0208 to the annual traffic signal contract R2017-0234 dated March 14, 2017, with Gerelco to provide for the furnishing and installation of various signal components for traffic control devices. The County desires to construct the project in accordance with the attached work order. The BCC's approval is required to authorize the construction of the project. The County received a check for \$400,000 for construction on July 28, 2017 from the developer, Home Dynamics Silverleaf, LLC, with any additional costs to be paid upon completion of the project. The estimated construction cost is \$208,335.50. A contingency of \$41,667.10 will be set aside, bringing the total fiscal impact to \$250,002.60 The developer, Home Dynamics Silverleaf, LLC, paid the design fees directly to the consultant, McMahon Transportation Engineers & Planners. Funds remaining after the completion of construction will be refunded to Home Dynamics Silverleaf, LLC.

Attachments:

- 1. Location Sketch
- 2. Work Order with Exhibits A and B, Bid Tabulation, and Signal Plan (3)

10 10		
Muc		1
Recommended By: _	David Lolley	4/4/18
	Department Director	Date
		•
Approved By:	- save IN Juhason	4/5/18
	Assistant County Administrator	Date

II. FISCAL IMPACT ANALYSIS

A. Five Year Summary of Fiscal Impact:

Operating Costs -0-	Fiscal Years Capital Expenditures	2018 2019	2020	2021 2022
External Revenues (\$250,003) -0000000000		\$250,003 -0-	<u>-0-</u>	00-
Program Income (County) -0-			0	0-
Program Income (County)		(<u>\$250,003)</u> 0-	0-	-0-
NET FISCAL IMPACT	Program Income (County)	0	-0-	
# ADDITIONAL FTE		00-	-0-	
		\$ -0-	-0-	-00-
POSITIONS (Comments 4th)				
1 OSITIONS (Cumulative)	POSITIONS (Cumulative)			

Is Item Included in Current Budget? Yes X No Does this item include the use of federal funds? Yes No X

Budget Account No:

Fund 1201 Dept 360

Unit 3224-170

Object 6408

Recommended Sources of Funds/Summary of Fiscal Impact:

County Transportation Trust Fund JPA & Developer Agreements/Trf Lantana Rd and Bentbrook Blvd/Gateway Terrace-Signalization

Annual Contract
New Work Order \$250,002.60
Developer Contribution (\$250,002.60)
Fiscal Impact .00

III. REVIEW COMMENTS

A. OFMB Fiscal and/or Contract Dev. and Control Comments:

JUNE POPUL 3/22/16

AFD OFMB BY 3/22/18 \$73/22

ontract Dev. and Control

B. Approved as to Form and Legal Sufficiency:

Assistant County Attorney

C. Other Department Review:

Department Director

This summary is not to be used as a basis for payment.

ż

I:\WP\AGENDAPAGE2\AGNPGTWO2018\18.129 SIGNAL.REV.DOC



WORK ORDER TO ANNUAL CONTRACT (R2017-0234) AS AMENDED (R2018-0208)
BETWEEN PALM BEACH COUNTY AND GERELCO TRAFFIC CONTROLS, INC.
TO CONSTRUCT A MAST ARM TRAFFIC SIGNAL TO REPLACE THE EXISTING
SPAN WIRE STRUCTURE AT THE INTERSECTION OF LANTANA ROAD AND
BENTBROOK BOULEVARD/GATEVIEW TERRACE,

PALM BEACH COUNTY INTERSECTION ID NUMBER 40015 SIGNAL PROJECT NUMBER 2017-57

PALM BEACH COUNTY PROJECT NUMBER 2017051 PALM BEACH COUNTY, FLORIDA

THIS WORK ORDER TO THE ANNUAL	CONTRACT R2018-0208, is made and
entered into this day of,	2018, by and between Palm Beach County,
a political subdivision of the State of Florida, by and the	hrough its Board of County Commissioners
("COUNTY"), and GERELCO TRAFFIC CONTR	ROLS, INC., a Florida corporation with an
address of 560 NW Enterprise Drive, Port Saint Lucie,	, FL 34986 ("CONTRACTOR").

WITNESSETH

WHEREAS, on March 14, 2017, the COUNTY and CONTRACTOR entered into an Annual Contract (R2017-0234) to provide for the furnishing and installation of various signal components for traffic control devices on a work order basis; and

WHEREAS, on March 13, 2018, the COUNTY approved the First Amendment (R2018-0208) to the Annual Contract to extend Annual Contract's expiration date from March 13, 2018 to March 13, 2019 ("CONTRACT"); and

WHEREAS, the COUNTY desires the CONTRACTOR to construct a mast arm traffic signal to replace the existing span wire structure at the intersection of Lantana Road and Bentbrook Boulevard/Gateview Terrace, Palm Beach County Intersection ID Number 40015, ("PROJECT"); and

WHEREAS, the CONTRACTOR agrees to construct the PROJECT in accordance with the terms and conditions of the CONTRACT, as directed and accepted by the COUNTY; and

WHEREAS, pursuant to the CONTRACT, a cost not to exceed \$250,002.60 has been calculated by COUNTY and found to be appropriate compensation for the services to be performed by the CONTRACTOR to construct the PROJECT.

NOW, THEREFORE, THIS INDENTURE WITNESSETH: That for and in consideration of the mutual benefits to flow from each to the other, the parties hereto agree as follows:

- 1. The CONTRACTOR agrees to provide services for the PROJECT in accordance with the CONTRACT and as further described in Exhibits "A" and "B"; and
- 2. The **COUNTY** agrees to pay the **CONTRACTOR** a fee not to exceed \$250,002.60 to construct the **PROJECT**. Final payment shall be per documented quantities installed.

Except as amended or modified, all other terms and conditions of the **CONTRACT** (R2018-0208) dated March 13, 2018 shall remain in full force and effect.

IN WITNESS WHEREOF, the parties hereto have made and executed this WORK ORDER as of the day and year first above written.

OWNER:	CONTRACTOR:
Palm Beach County, Florida by its Board of County Commissioners BY:	Gerelco Traffic Controls, Inc. a Florida Corporation BY:
Melissa McKinlay, Mayor	Kenneth A. Geremia, Jr., President
ATTEST: Sharon R. Bock, Clerk & Comptroller Circuit Court	CORPORATE S E A L
BY: Deputy Clerk	WITNESS:
SEAL	Brandy Coble (Printed Name)
APPROVED AS TO TERMS AND CONDITIONS:	BY: Millie Barbosa Millie Barbosa
BY: McConnell (Printed Name)	(Printed Name)
APPROVED AS TO FORM & LEGAL SUFFICIENCY:	
BY: Yelizaveta B. Herman Assistant County Attorney	

EXHIBIT "A"

PALM BEACH COUNTY ENGINEERING & PUBLIC WORKS TRAFFIC DIVISION WORK ORDER / ANNUAL CONTRACT R2018-__0208

PROJECT NAME: Lantana Road and Bentbrook Boulevard/Gateview Terrace

(PBC Intersection 40015)

BUDGET LINE ITEM: <u>1201-360-3224-170-6408</u>

KDO NUMBER: KDO 360 EN011818-112

PBC ENGINEERING ANNUAL PROJECT NUMBER: 2017051 PBC ENGINEERING SIGNAL PROJECT NUMBER: 2017706

PBC TRAFFIC DIVISION SIGINAL CONTRACT PROJECT NUMBER: 2017-57

WORK ORDER NUMBER: 7G

DATE: 2/20/18

COMMISSION DISTRICT: 3

TO: Kenneth A. Geremia, Jr., Gerelco Traffic Controls, Inc.

In accordance with the terms of your contract dated March 13, 2018, you are directed to provide the following supplies and services: Provide for the furnishing and installation of a mast arm traffic signal to replace existing span wire structure as shown on the Signal Plan on pages 1 thru 5, and Bidtab, dated December 15, 2017.

The above work shall be performed at: <u>Lantana Road and Bentbrook Boulevard/Gateview Terrace</u> (PBC Intersection 40015).

STARTING: The contract duration for this work is <u>240</u> days. A separate Notice to Proceed ("NTP") letter will be issued directing the contractor to commence work within the time specified in the NTP letter. The total amount of this Work Order, at the contract prices, is estimated to be \$250,002.60, which includes \$41,667.10 contingency (See attached bidtab for quantities). Final payment shall be per documented quantities installed. The Small Business Enterprise (SBE) goal for this contract is <u>23.1%</u>. The estimated SBE Participation for this Work Order is <u>35.9%</u>. The total SBE participation to date for this Contract is <u>17.7%</u>.

This work shall be coordinated by, (48 hours prior notice to commencement of work):

Fattoush Jafar, P.E., Ph.D, Senior Professional Engineer (561) 684-4030

Name	Title	Telephone
Please indicate you	r receipt of this Work Order b	y signing and returning a duplicate copy.
	President	7723167474
Name Kenneth A.	Geremia, r. Title	Telephone
_	nd submit with invoice at the n compliance with Contract a	
Signature	Title	Telephone

SCHEDULE 1 LIST OF PROPOSED SBE-M/WBE PRIME AND/OR SUBCONTRACTOR PARTICIPATION

PROJECT NAME OR BID NAME:	Lantana / Bent	brook	PROJECT NO	O. OR BID NO.:	2017-51		
NAME OF PRIME BIDDER:	Cereko Truffic Co	ontrols. Inc	ADDRESS:	560 ww	ENTERPOILS.	Dr. PSL.	FL. 34986
CONTACT PERSON:	Jake Ridinger		PHONE NO.:	772 - 340	7474 FAX	(NO.:	
BID OPENING DATE:	-	·	USER DEPAI				
THIS DOCUMENT IS TO BE COMI AMOUNT OR PERCENTAGE OF W NAME, CONTACT INFORMATION, MONITOR THE SBES LISTED TO EN	AND DOLLAR AMOUNT OR PE	LL SBE-M/WBE SUBCON RCENTAGE OF WORK TO	TRACTORS ON T O BE COMPLETE	THIS PROJECT. IF T	THE PRIME IS AN !	CRE_M/WRF PIFA	OF AT SOLT TOT TOTAL
	(Check on <u>M/WBE</u>	e or both Categories) <u>SBE</u>		DOLLAR AMO	OUNT OR PERCENT	AGE OF WORK	
Name, Address and Phone N	umber Minority Busin	ess Small Business	Black	Hispanie	Women	Caucasian	Other (Please Specify)
1. T. I Electric				-			74,569
2.			1.1				
2.							
							
3.							
4.							
(Please use additional sheets, if necessary	y)	m . 1					
		Total					
Total Bid Price: \$. 335 . 50	Total SBE-M/WBE I	Participation Dollar	Amount or Percentage		74,56°C	<u> </u>
I hereby certify that the above information	tion accurate to the best of my know	ledge: Signature	H	Troje	F Maraga	1 2	/22/18
2. Firms may be certified by Pa	rm for a subcontractor must be suppor alm Beach County as an SBE and/or M g collected for tracking purposes only.	ted by price or percentage list I/WBE. If firms are certified:	ted on the signed Sci as both an SBE and	nedule 2 or signed propo M/WBE, please indicate	sal in order to be count the dollar amount or p	ed toward goal attainn ercentage under the ap	nent. propriate category. Revised 9/7/2011

OSBA SCHEDULE 2 LETTER OF INTENT TO PERFORM AS AN SBE-M/WBE SUBCONTRACTOR

This document must be completed by the SBE-M/WBE Subcontractor and submitted with bid packet. Specify in detail, the particular work items to be performed and the dollar amount and/or percentage for each work item. SBE credit will only be given for items which the SBE-M/WBE Subcontractor is SBE certified to perform. Failure to properly complete Schedule 2 may result in your SBE participation not being counted.

PROJECT NUMBER: 2017 - 57 PROJECT TO: Correle Time Fore Control	•	intana Rol / Ber	ntbrook Rd
(Name of P	rime Bidder)	те с 1	
The undersigned is certified by Palm Beach County as a (check	one or more, as ap	oplicable):	
Small Business Enterprise	Enterprise Caucasian	Other (Pleas	e Specify)
Date of Palm Beach County Certification:	er om till der er staten milit der der er sammel film dem er er staten bestelle er en		telle with the second for a consequent of the second or th
The undersigned is prepared to perform the following described be used as necessary):	work in connectio	n with the above project (additional sheets may
Line Item/ Lot No. Item Description 649-31-107 Martacon D3-522	Qty./Units	Unit Price	Total Price/ Percentage 52.809
649-31-108 Mustarm D5-523		21,761	2),761
at the following price or percentage: 74,569	(Subcontrac	ctor's Quote)	
and will enter into a formal agreement for work with you conditi			
If undersigned intends to subcontract any portion of this job name of the subcontractor and the amount below.	to a certified SBE	E or a non-SBE subcontra	actor, please list the
Price and/or Percentage			<u> </u>
•	(N	ame of Subcontractor)	
The Prime affirms that it will monitor the SBE's listed to ensure t subcontractor affirms that it has the resources necessary to perfor any other certified SBE subcontractors except as noted above.			
The undersigned subcontractor understands that the provision of providing quotations to other bidders.	f this form to Prim	e Bidder does not prevent	Subcontractor from
Coerpico Traffic Confrol Print Name of Prime Contractor] I Pjint	Elecine. U	
By:	By 6	Signature	her
Take Rainger Project Manager Print Name/Title of Person Executing on Behalf of Prime Contractor	Print Nan	ISH Wahabi ne/Title of Person Execution SBE/M/WBE Subcontra	Y - Kresident.
Revised 10/11/2011	Date:	2/6/2018	3



PBCBCC-TRAFFIC DIVISION 2300 N. JOG ROAD W.P.B., FL. 33411-2745

Phone: (561) 684-4030 Fax: (561) 478-5770

GERELCO BIDTAB CONTRACT #2017051

DATE:

12/15/2017

CONTRACT NO.#:

2017-57

***************************************			Name of the Party
	Harrist State of the Control of the	prook Blvd/Gateview Ten	
A STATE OF THE PARTY OF THE PAR			
经工工工业的企业的企业工程的企业工程的企业工程的企业工程的企业工程			A STATE OF THE PARTY OF THE PAR

ITEM NO.#	PRODUCT NAME	QTY	PRICE	LINE TOTAL
102-1-A	GENERAL MAINTENANCE OF TRAFFIC - [HR] [F&I]	16	\$126.00	\$2,016.00
630-2-11-2	2" PVC (SCH 40) UNDERGROUND CONDUIT - [LF] [F&I]	298	\$8.00	\$2,384.00
630-2-11-2A	ADDITIONAL 2" PVC (SCH 40) CONDUIT, IN OPEN TRENCH - [LF] [F&I]	315	\$2.50	\$787.50
630-2-12-2-5	5-2" (HDPE SDR 11) UNDER PAVEMENT CONDUIT (DIRECTIONAL BORE) - [LF] [F&I]	550	\$30.00	\$16,500.00
632-7-1-19F	SIGNAL CABLE (SPAN LENGTH 651' - 750') - [PI] [F&I]	1	\$3,600.00	\$3,600.00
632-7-1-4A	PEDESTRIAN SIGNAL CABLE - 4 CONDUCTOR - [PI] [F&I]	1	\$1,063.00	\$1,063.00
632-7-1-7A	PEDESTRIAN SIGNAL CABLE - 7 CONDUCTOR - [PI] [F&I]	1	\$2,809.00	\$2,809.00
635-2-12-A	PULL BOX (17" x 30" x 12"D) HEAVY DUTY COVERS - [EA] [F&I]	20	\$850.00	\$17,000.00
635-2-13-A	PULL BOX (30" x 48" x 24"D) HEAVY DUTY SPLIT COVERS (ITS) - [EA] [F&I]	1	\$1,835.00	\$1,835.00
639-1-123	ELECTRICAL POWER SERVICE (UNDERGROUND) - [AS] [F&I]	1	\$850.00	\$850.00
639-2-1	ELECTRICAL SERVICE WIRE (SINGLE PHASE 3-WIRE, TRIPLEX) - [LF] [F&I]	60	\$2.30	\$138.00
639-3-11	ELECTRICAL SERVICE DISCONNECT - [EA] [F&I]	1	\$325.00	\$325.00
641-2-12-12	PRESTRESSED CONCRETE POLE (12' TYPE P-II) - [EA] [F&I]	1	\$750.00	\$750.00
641-2-70A	CONCRETE POLE REMOVAL - SHALLOW (INCLUDES POLE AND BURIED ATTACHMENTS TO A DEPTH OF 4	4	\$2,465.00	\$9,860.00
646-1-11	ALUMINUM SIGNALS POLE, PEDESTAL WITH TRANSFORMER BASE (8 FEET ABOVE GROUND) - [EA]	8	\$770.00	\$6,160.00
649-31-107	MAST ARM ASSY D3-S22 46' W/LUM (POWDER COATED FINISH) - [EA] [F&I]	3	\$27,567.00	\$82,701.00
649-31-108	MAST ARM ASSY D5-S23 60' W/LUM (POWDER COATED FINISH) - [EA] [F&I]	1	\$31,318.00	\$31,318.00
649-38-000-E	ADDITIONAL DEPTH FOR MAST ARM ASSEMBLY FOUNDATION (WHEN SPECIFIED BY ENGINEER) - [LF]	1	\$650.00	\$650.00
650-1-13	TRAFFIC SIGNAL HEAD ALUMINUM (3-SECTION, 1-WAY) INCLUDES BACKPLATES - [AS] [F&I]	6	\$900.00	\$5,400.00
650-1-14	TRAFFIC SIGNAL HEAD ALUMINUM (4-SECTION, 1-WAY) INCLUDES BACKPLATES - [AS] [F&I]	2	\$1,020.00	\$2,040.00
650-1-15	TRAFFIC SIGNAL HEAD ALUMINUM (5-SECTION, 1-WAY) INCLUDES BACKPLATES - [AS] [F&I]	2	\$1,350.00	\$2,700.00
650-1-70	TRAFFIC SIGNAL HEAD ASSEMBLY, REMOVAL - [EA] [R]	9	\$95.00	\$855.00

DATE:

12/15/2017

CONTRACT NO.#:

2017-57


INTERSECTION:	Lantana Rd and Bentbrook Bl	vd/Gateview Terr	

ITEM NO.#	PRODUCT NAME	QTY	PRICE	LINE TOTAL
653-191	PEDESTRIAN SIGNAL - COUNT DOWN (1-WAY) ALUMINUM - [EA] [F&I]	8	\$650.00	\$5,200.00
660-4-30-A4	VIDEO IMAGE DETECTION 4 - CAMERA SYSTEM (AUTOSCOPE) - [EA] [I]	1	\$1,280.00	\$1,280.00
665-1-11	PEDESTRIAN DETECTOR (PUSH BUTTON) - [EA] [F&I]	8	\$95.00	\$760.00
670-5-310	TRAFFIC CONTROLLER ASSEMBLY (TYPE 5 - INSTALL ONLY) - [AS] [I]	1	\$2,850.00	\$2,850.00
690-20	SIGNAL PEDESTRIAN ASSEMBLY, REMOVAL - [EA] [R]	8	\$46.00	\$368.00
690-31-1	SIGNAL PEDESTAL, REMOVE - [EA] [R]	4	\$75.00	\$300.00
690-50-0	REMOVE CONTROLLER ASSEMBLY COMPLETE WITH FOUNDATION - INCLUDES DELIVERY OF REMOVED	1	\$1,250.00	\$1,250.00
690-70	REMOVE PEDESTRIAN DETECTOR ASSEMBLY - [EA] [R]	8	\$12.00	\$96.00
690-80	REMOVE SPAN WIRE ASSEMBLY - [PI] [R]	1	\$1,250.00	\$1,250.00
700-5-42	INTERNALLY ILLUMINATED SIGN (8') INSTALL ONLY - [EA]	4	\$750.00	\$3,000.00
715-5-50	LUMINAIRE & BRACKET ARM - REMOVE - [EA] [R]	4	\$60.00	\$240.00


TOTAL:

\$208,335.50

Comments: Signal Modification / New Mast Arms



ALL MAST ARM INSTALLATIONS TO MEET FOOT SPECIFICATIONS AND HAVE THE COLOR OF "VERDE GREEN". THE PAINT APPLICATION SHALL BE WARRANTED FOR 5 YEARS AS SPECIFIED IN THE CURRENT EDITION OF THE FOOT SPECIFICATIONS. ALL MAST ARM UPRIGHTS TO MAVE A 20-POSITION TERMINAL STRIP COMPARTMENT AT THE BASE. TERMINAL STRIPS (SOREWS TO BE STAMLESS STEEL. STAMLESS STRAIN RELIEF DEVICES ARE TO ENCLOSE ALL SIGNAL CABLES WITHIN MAST ARM UPRIGHT AND BE ATTACHED TO THE J-HOOK.



* DENOTES NUMBER OF	SECTIONS II	N SIGNAL	HEAD	ASSEMBLY
---------------------	-------------	----------	------	----------

											CLCAL																											
			T	_	т	┼					SIGN	AL E	PATA															51	GN D	ATA							٦	
ID NO.	SHEET NO.	LOCATION BY 5TA.	TOP OF FOUNDATION ELEVATION	ARM	CROWN ELEV.	SIGNAL	PLATES	SIGNAL			L	DIST	NCE	FROM	POLI	·			TOTAL	ARM	4 BETWEEN DUAL ARMS				D	ISTANC	E FROI				ND WIL	TH OF	SIGN				VIDEO	
A	T-X	40244F 07 (04 F411 T)		#O.			Y/N	Y/N	1	*	2	*	3	*	4	*	5	•	ARM LENGTH	M.H.	90/270	A	н1	WI		H2	W2	С	нз	wз		H4		т	T		DETECTOR	COLOR
_	1*/	102+45.05 (64.54' LT)	20.55	1	21,23	V	Υ .	N	27'	3	39'	3	47'	5				\Box	52'	22		13'	2'	B'	┝╌	+	···		1 113	113	U	H4	W4	E	H5	W5	DISTANCE	
В	T-X	103+55.69 (69.62°LT)	21,08	1	20.50	+v	V	N	26'	١,	39'	4		\bot		П								۲	 	+-	_		+	├	┼	╫─	┼	├──	┼		42' (V1)	POWDER COATE
						Ť	一	 " -	20	+-	39	+	├─	-	<u> </u>	1-1		+	44'	21		18'	2'	6'					\vdash		 	+-	+	 	+	├─	32' (V2)	VERDE GREEN
С	T-X	103+75.49 (57.25' RT)	21,20	1	20.87	V	Y	N	17'	3	28'	3	39'	- 5		+		+	44'	21		401	<u> </u>												+-	\vdash	32 (VZ)	POWDER COATE VERDE GREEN
D	T-X	102+47,80 (93,24' RT)	04.50	<u> </u>										1		11		+		21		10'	2'	8'	-	+			1								31' (V3)	POWDER COATE
	1-7	102747.00 (85.24 KT)	21.50	1	20.90	V	Y	N	29'	3	41'	4				\Box		\Box	46'	21		14'	2'	6'			_		┼	<u> </u>	₩	╀			┸			VERDE GREEN
			}		 -	┼			_	4		4		\perp								•	† <u> </u>	۰	_	+			┼	├	-	-	┼	—	┼—	₩	35' (V4)	POWDER COATE
					 	┼──	 	├	├	+		+		-		11													+	├──	┼	+	┼	├──	┼	┼	-	VERDE GREEN
						1	 	\vdash	\vdash	+-		+-	<u> </u>	+		1		\sqcup											†	-	 	+-	+	├─	+-	┼	 	-
						T				+		+-	├──	+-		+		+						<u> </u>										\vdash	_	\vdash		
												+	 	+		++		+					<u> </u>	<u> </u>											†			1
																1-1		+							├													
			<u> </u>	\vdash		 												+						+	├				ـــ	<u> </u>		_						
								<u> </u>	<u> </u>	4													 	 -	┼	+			┼	├		+-		—	ـــــ			
								├	├	+-		+-		1		\Box							1	t	1	+-	-		┼	├	+	┼—	┼	├─	₩	—	 	
					<u> </u>			1	<u> </u>				L										1	T		1-			+	+	+	+	+	├─	┼	—	 	4

PBCO INTERSECTION NUMBER 40015

050 PALM BEACH LINES BLVD. SUITE 400 (SSI) BAC-BS WEST PALM BEACH, FL 35409 FAX (SSI) BAC-BSSO CERTIFICATE OF AUTHORIZATION NO. 4508 E.D.R. R. TRENT EBERSOLE, P.E. P.E. NO. <u>64389</u>

OWNER	Lantana Farm Associates, Inc.	PROJECT:	TASK:
	Lantana Farm Consultants, Inc.	LANTANA FARMS P.U.D.	+
	P.O. BOX 541779		┪
	Lake Worth, Fl. 33454-1779	PALM BEACH COUNTY FLORIDA	┪

	DESIGNED BY:	J DH	SEALED:
	DRAWN BY:	JDH	
MAST ARM TABULATION	CHECKED BY:	RTE	
	AUGUST 2016		1

		REVISIONS	
NO. DA	TE BY	DESCRIPTION	SHEET NO.
			T-6

						STAND	ARD MA	AST ARM	ASSEI	MBLIES	DATA 1	TABLE								
STRUCTURE	(1)	F	IRST AR		51	ECOND A	RM				PC	LE		SPECIAL DRILLED SHAFT (4)						
ID NUMBERS	ASSEMBLY NUMBERS	ARM TYPE	(2) FAA (ft.)	(2) FBA (in.)	ARM TYPE	(2) FAA (ft.)	(2) FBA (in.)	UF (deg)	(deg)	POLE TYPE	(3) UAA (ft.)	UB (ft.)	(3) UCA (in.)	DA (ft.)	DB (ft.)	RA	RB	RC	RD (in.)	
Α	D5-S23	D5	27.8	9.11					90	\$23		22							 	
В	D3-\$22	D3	34.1	9.23					45	\$22		21		12.5	4.5	11	15	10	12	
С	D3-S22	D3	34.1	9,23					90	S22		21		12,5	4.5	11	15	10	12	
D	D3-S22	D3							90	S22		21						10	 "	

TABLE NOTES:

Assembly Number Legend

Single Arm: Arm Type - Pole Type = D# - S# = E# - T# = F# - W#

Double Arm:
First Arm Type - Second Arm Type - Pole Type = D# - D# - S#
= E# - E# - T#

- If an entry appears in columns "FAA" and "FBA", a shorter arm is required.
 This is obtained by removing length from the arm tip. For these cases the mast
 arm length shall be shortened from "FA" to "FAA" and the tip diameter shall
 be increased from "FB" to "FBA".
- If an entry appears in columns "UAA" and "UCA", a shorter pole is required.
 This is obtained by removing length from the pole tip. For these cases the pole height shall be shortened from "UA" to "UAA" and the pole tip diameter shall be increased from "UC" to "UCA".
- 4. The foundations for Standard Mast Arm Assemblies are pre-designed and are based upon the following conservative soil criteria which covers the great majority of soil types found in Florida. Only complete the "Special Drilled Shaft" data information if site conditions dictate drilled shafts with additional foundation capacity.

Classification = Cohesionless (Fine Sand)
Friction Angle = 30 Degrees (30^)
Unit Weight = 50 lbs. / cu. ft. (assumed submerged)
N-blowcount = 15

GENERAL NOTES:

- Work this sheet with the Signal Designer's "Mast Arm Tabulation". See "Mast Arm Tabulation" for special instructions that include non-standard Handhole location, paint color, terminal compartment requirement, and pedestrian features.
- 2. Work with Index Nos. 17743 and 17745.
- 3. Design Wind Speed = 150 mph
- 4. Contractor shall coordinate anchor bolt requirements with fabricator.
- 5. Contractor shall identify Structures Numbers and submit detailed shop drawings.

FOUNDATION NOTES:

- Design based on Borings taken on 5/22/2008 sealed by Ryan Bridger, P.E., ECS LLC
- 2. Assumptions and Values used in design:

Mast Arm Structure A (Boring B-1)
Soil Type = Fill; SM / SC / SP
Soil Layer Thickness = 14 ft.
Soil Friction Angle = 30 deg.
Submerged Soil Unit Weight = 57.6 pcf
Weighted N value = 13.43
Design Water Table is 6.5 ft. below surface

Mast Arm Structure B (Boring B-2)
Soil Type = Fill; SP / SM / SP
Soil Layer Thickness = 12 ft.
Soil Friction Angle = 30 deg.
Submerged Soil Unit Weight = 57.6 pcf
Weighted N value = 8.67
Design Water Table is 5.5 ft. below surface

Mast Arm Structure C (Boring B-3)
Soil Type = Fill; SP / SM / SP
Soil Layer Thickness = 12 ft.
Soil Friction Angle = 30 deg.
Submerged Soil Unit Weight = 57.6 pcf
Weighted N value = 16.50
Design Water Table is 6.5 ft. below surface

Mast Arm Structure D (Boring B-4)
Soil Type = Fill; SP / SM / SC / SP
Soil Layer Thickness = 12 ft.
Soil Friction Angle = 30 deg.
Submerged Soil Unit Weight = 57.6 pcf
Weighted N value = 13.83
Design Water Table is 6.5 ft. below surface

PBCO INTERSECTION NUMBER 40015

EGG PALI BEACH LAKES BUILD SUITE 400 (561) 640-8650
WEST PALI BEACH, FL 3346F FAX (581) 640-8650
WEST PALIF BEACH, FL 3346F FAX (581) 640-8650
E.O.R. F. TRENT LERESOLE, P.E.
P.E. NO. 54396

Lantana Farm Associates, Inc.

Lantana Farm Consultants, Inc.

P.O. BOX 541779

Lake Worth, Fl. 33454-1779

PALM BEACH COUNTY

FLORIDA

= F# - F# - W#

MAST ARM ASSEMBLIES DATA TABLE


TASK:

DESIGNED BY: JDH

DRAWN BY: JDH


CHECKED BY: RTE

AUGUST 2016



SERVICE DETAIL FOR SIGNALIZATION AND MAST ARM LUMINAIRES NOT TO SCALE

NOTE: SEE INDEX 17504 FOR ADDITIONAL INFORMATION.



FIBER TERMINATION DETAIL

PBCO INTERSECTION NUMBER 40015

OWNER: Lantana Farm Associates, Inc.

PROJECT:

TASK:

DESIGNED BY: JDH | SEALED:

REVISIONS

DOO PALM BEACH LAKES BLYD. SUITE 400 156/1040-0650 WEST PALM BEACH, FL 33409 FAX 156/1040-0650 CERTLE BEACH, FL 33409 FAX 156/1040-0650 E.D.R. R. TRENT EBERSOLE, P.E. Lantana Farm Consultants, Inc. LANTANA FARMS P.U.D.
P.O. BOX 541779
Lake Worth, Fl. 33454-1779
PALM BEACH COUNTY FLORIDA

SIGNALIZATION DETAILS

DRAWN BY: JDH
CHECKED BY: RTE
AUGUST 2016

NO. DATE BY DESCRIPTION SHEET NO.

